



STIFFENED BIN CONSTRUCTION MANUAL

Farm Stiffened, 15' - 48' Dia., 5K Roof

Roof rating is based on weight evenly distributed on peak ring as pure vertical load with uniformly distributed roof snow load calculated from 40psf ground snow zone or 105 mph wind zone as defined by ASCE 7-16 Code.



<u>DATE</u>	<u>REVISION</u>	<u>SECTION</u>
03/2025	– Updated description of bin height in anchor bolts table.....	Anchor Bolts
	Clarified instructions for attaching roof sheets to apron	Roof
	Corrected part number for manhole cover anchor bracket.....	Roof
	Added note on disregarding J-hook installation if bin does not have a stirring machine.....	Roof
	Updated ladder & platform drawings as needed	Ladders
	Added guide for locating Greene sidewall stairs manual if Greene stairs were ordered.....	Stairs

Sukup Manufacturing Co.

1555 255th Street, Box 677

Sheffield, Iowa, USA 50475-0677

Phone: 641-892-4222

Fax: 641-892-4629

Website: www.sukup.com

E-mail: info@sukup.com

IMPORTANT: KEEP GALVANIZED SHEETS DRY BEFORE ERECTING!

If this material is allowed to get wet or condensation is permitted to form between sheets, discoloration may occur.

- Upon receiving material, check for moisture between sheets. Do not permit moisture from weather, condensation or other sources to remain between sheets.
- To help prevent white rust, store sheets away from moisture. Store under cover in a heated building with adequate air circulation if lengthy storage or adverse weather conditions are expected. Never allow water to stand on sheets or bundles.
- Sheets covered with tarpaulin or polyethylene should have enough space between cover and sheets to allow air to circulate.
- If bundle gets wet, dry all materials immediately. Stack sheets on edge in a dry place and force air between them. Allow for free passage of air around each sheet when practical.
- NEVER lay steel on earth. Store on timber or blocks. Always store material on a dry, solid surface in a manner that allows moisture to run off of material.
- DO NOT apply any solvents or lubricants to sidewall sheets.

Damage resulting from failure to take appropriate actions listed above will void Sukup Manufacturing Co. warranty.

IMPORTANT: Sukup Manufacturing Co. must be notified within 72 hours of pickup or delivery if any materials are rusted. Sukup is not responsible for rusted materials discovered after the 72-hour period. Sukup accepts no responsibility for stains, corrosion or other damage to sheets while stored at construction site.



Sukup Manufacturing Co.
PO Box 677 Sheffield, IA USA 50475
Phone: 641-892-4222 Fax: 641-892-4629
E-mail: Info@sukup.com Visit us at: www.sukup.com

GRAIN BIN LIMITED WARRANTY

SUKUP MANUFACTURING CO. (Sukup) warrants, to original retail purchaser within 5 years from date of purchase, that grain bin shall be free from defects in material and workmanship. A part will not be considered defective if it substantially fulfills performance specifications, including, but not limited to, parts with cosmetic (appearance) issues that will not affect life of the structure. Should any part prove defective within warranty period, part will be replaced or repaired without charge F.O.B. Sukup Manufacturing Co., Sheffield, Iowa USA or Distribution Centers - Arcola, Illinois; Aurora, Nebraska; Cameron, Missouri; Defiance, Ohio; Jonesboro, Arkansas; Watertown, South Dakota. To claim warranty, a copy of original invoice is required.

WARRANTY CERTIFICATION - Warranty must be registered within one month of product delivery to certify warranty coverage. See QR code on back page of Bin Operation Manual for details.

THE FOREGOING LIMITED WARRANTY IS EXCLUSIVE AND IN LIEU OF ALL OTHER WARRANTIES OF MERCHANTABILITY, FITNESS FOR PARTICULAR PURPOSE AND OF ANY OTHER TYPE, WHETHER EXPRESS OR IMPLIED. Sukup neither assumes nor authorizes anyone to assume for it any other obligation or liability in connection with said part, and will not be liable for incidental or consequential damages. THE REMEDIES STATED HEREIN SHALL BE THE EXCLUSIVE REMEDIES AVAILABLE UNDER THIS LIMITED WARRANTY.

Sukup reserves the right to change specifications, add improvements or discontinue manufacture of any of its equipment without notice or obligation to purchasers of its equipment. This warranty gives you specific legal rights. You may also have other rights which vary according to state or province.

WARRANTY EXCLUSIONS - Labor, transportation, or any cost related to a service call is not provided by Sukup. This Limited Warranty does not apply to damage resulting from misuse, neglect, normal wear, accident or improper installation or maintenance. **ITEMS NOT MANUFACTURED BY SUKUP ARE COVERED UNDER WARRANTIES OF THEIR RESPECTIVE MANUFACTURERS AND ARE EXCLUDED FROM COVERAGE UNDER THE SUKUP WARRANTY. SUKUP MANUFACTURING CO. MAKES NO WARRANTY, EXPRESS OR IMPLIED, OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.**

Foundation recommendations are suggestions only and will vary according to local soil conditions. Soil bearing tests must be performed by a competent, independent engineering firm. Sukup will not assume responsibility for adverse result arising from their use. Sukup will not warrant damage or loss caused, in whole or in part, by inadequate or improper site selection, site preparation, foundation, or any other failure to provide a suitable erection or installation environment for Sukup grain bin or of any product, component, equipment, accessories, parts used in conjunction with Sukup grain bin. Sukup will not warrant damage or loss caused, in whole or in part, by use of bin in a manner other than for which it was designed, or by unauthorized attachments, modifications, alterations, improper or inadequate maintenance, misuse or abuse of the bin.

Sukup is not liable for direct, indirect, incidental or consequential damages, including, without limitation, loss of anticipated profits or benefits. Not responsible for field modifications or erection defects which create structural or storage quality problems.

WARRANTY IS VOID - If not purchased from or constructed by an authorized dealer or a representative of Sukup Manufacturing Co.; If used for substances other than grains and/or free flowing materials.

Prior to installation, purchaser has responsibility to properly store steel bin components. Bin should be stored in dry, temperature and humidity controlled areas to eliminate condensation and other moisture that causes white rust and corrosion. Warranty does not extend to defects, damages or cosmetic (appearance) issues caused by improper storage or handling.

Sukup does not warrant any roof damage caused by excessive vacuum or internal pressure from fans or other air moving systems. Adequate ventilation and/or "make-up air" devices should be provided for all powered air handling systems. Warranty is void if grain is above eave and against roof, as this will block roof vents and cause unwanted loads on roof sheets. Area above surface of grain must allow free movement of air to vents. Sukup does not recommend use of downward flow systems (suction). Severe structural roof damage may occur if fans or other air moving devices are operated during certain high humidity/cold weather conditions. Roof ventilators may frost over and plug or restrict air flow causing excessive vacuum or internal pressures. Roof damage may occur due to improperly installed grain temperature detection cable systems.

Sukup does not warrant failures due to filling bin off-center; unloading from door or off-center floor sump; or radial cracks in foundation. If bin has a perforated floor on columns and columns fail, bin can shift sideways causing both sidewall and roof damage.

UNAPPROVED PARTS OR MODIFICATION - All obligations of Sukup under this warranty are terminated if unapproved parts are used, equipment is modified or altered in any way not approved by Sukup in writing, or is not erected or operated according to Sukup installation or operating manuals.

12/12/23

Table of Contents


Important Message	2
Limited Warranty	3
Safety Section	5-15
Foundation & Anchor Locations	16-32
Farm Anchors	33-34
5K Roof Assembly	35-57
Farm Stiffened Sidewall	58-66
Wind Ring	67-68
Farm Door	69-74
Ladders, Safety Cages & Platforms	75-106

IMPORTANT

Please read entire Bin Operation Manual and Construction Manual, paying close attention to safety sections. Failure to read these manuals is a misuse of the product and could result in death or personal injury or property damage. All personnel associated with the bin must read these manuals thoroughly as well.

Although every effort is made to ensure assembly drawings and instructions are written without errors, they may happen. Therefore, if any concerns arise regarding any instructions or assembly drawings, please contact Sukup Manufacturing Co. customer service immediately for clarification prior to proceeding with construction.

Recognizing Safety Decal Information

 Read manual before installing or using product. Failure to follow instructions and safety precautions in manual can result in death or serious injury. Keep manual in a safe location for future reference.



On safety decals, this symbol and the signal words Danger, Warning, Caution and Notice draw your attention to important instructions regarding safety. They indicate potential hazards and levels of intensity.



RED - **DANGER** indicates an imminently hazardous situation which, if not avoided, will result in death or serious injury.



ORANGE - **WARNING** indicates a potentially hazardous situation which, if not avoided, could result in death or serious injury.




YELLOW - **CAUTION** indicates a potentially hazardous situation which, if not avoided, may result in minor or moderate injury.



BLUE - **NOTICE** alerts you to practices unrelated to personal injury, such as messages related to property damage.

IMPORTANT: To prevent serious injury or death to you or your family, be certain that all decals are in place according to illustration below and are legible. If a suggested location is not clearly visible, place decal in a more suitable area. Additional safety decals are available at no charge for Sukup equipment. Please specify decal number when ordering. See contact information on cover of manual.



1 LADDER WARNING - Decal L0164

Mount on bin sheet next to ladder or stairs. Attached in advance on inside bin door and on manhole sheet so it can be seen by anyone entering bin.

2 "DANGER DO NOT ENTER" - Decal L0258A

Mount on bin sheet next to ladder or stairs. Attached in advance on inside of bin door and on manhole sheet so it can be seen by anyone entering bin.

3 "WARNING DO NOT ENTER THIS BIN! Keep clear of all augers."

If you must enter the bin:

- Shut off and lock out all power.
- Use a safety harness and safety line.
- Station another person outside the bin.
- Avoid the center of the bin.
- Wear proper breathing equipment or respirator.
- Follow applicable safety regulations.

Failure to heed these warnings will result in serious injury or death.

4 "WARNING TO AVOID SERIOUS INJURY" - Decal L0281

Mount decal on bin sheet next to ladder or stairs. Attached in advance on inside of bin door so it can be seen by anyone entering bin.

5 "WARNING DO NOT OVERFILL BIN" - Decal L0906

Attached in advance on manhole sheet so it can be seen by anyone entering bin.

6 "WARNING CLOSE DOOR TIGHTLY..." - Decal L0909

Attached in advance on outside of inner door panel.

General Operational Safety Procedures



WARNING: Make hazards known to all personnel working in area so they can take appropriate safety precautions. Failure to follow precautions listed below may cause death or serious injury.

- Hands, feet and clothing must be kept away from moving parts. Loose clothing can become entangled in moving parts and cause serious injury.
- Be aware of danger that is present when loading and unloading bin. Flowing and crusted grain can trap and suffocate.
- Do not enter bin without having an observer outside who is in constant contact with you.
- Decals with specific messages are attached to equipment at various locations. Pay attention to messages and always be alert to the possibility of personal injury or death.
- Keep all guards and shields in place and secure while machines are in operation.
- Ladders and working surfaces should have safety cages and handrails for safe use. Use a lifeline and harness when danger of falling exists.
- Keep bystanders and children away from grain bins and grain handling equipment. **Bin sites are not playgrounds!**
- Bins must be labeled to warn of entrapment and flowing grain hazards.
- Proper operational procedures must be followed to ensure safety and well-being of all persons working near or on grain bins when inspecting grain, performing maintenance or spraying insecticides.
- Hazards associated with grain bins include engulfment in grain, falls from heights, dust and mold inhalation, pesticide exposure, electrocution, and injuries from augers. Take precautionary steps to avoid these hazards.
- Learn how to use controls and operate equipment correctly. Do not let anyone operate unit (especially youth) without thorough training of basic operating and safety procedures.
- Periodically check all mechanical and electrical components to keep them in good working condition. Make no unauthorized modifications to equipment. Doing so may endanger function and safety of unit.
- Be aware of weather-related safety hazards. Icicles and snow falling from bin eave are dangerous and can cause serious injury or death. Ice or moisture on ladders can cause slippery conditions that may result in a life-threatening fall.
- For added security and safety, attach a padlock to sidewall door latch.
- If you must enter bin, shut off equipment and lock out all power sources before entering; keep clear of all moving parts; use a safety harness and safety line, station another person outside of bin; avoid center of bin; wear proper breathing equipment or respirator; follow applicable safety regulations; ensure quick access to an ABC dry chemical fire extinguisher.

Dangers of Entering a Grain Bin




No one should enter a grain bin while it is being loaded or unloaded due to risk of being injured by moving parts such as augers or being crushed and/or suffocated by grain. Entering a bin that has bridged or crusted grain is very dangerous. Working in a grain bin without following proper safety procedures increases an individual's chance of being suffocated. If grain is peaked close to roof, do not enter bin. Crawling between roof and peak could cave grain and block exit.

Owners/operators are responsible for developing site-specific confined space entry procedures. OSHA's confined space entry procedures (29CFR 1910.146) can be found at www.osha.gov.

Flowing & Crusted Grain

People can become caught or trapped by grain in several ways: entrapment by flowing grain, collapse of bridged grain, and collapse of a vertical wall of grain. To better understand why grain flow is so dangerous, you must understand how grain flows when it is unloaded. Grain bins are first emptied through the center sump (bins erected with a sidedraw are only exception). When center sump is opened and auger is started, grain flows from top surface down a center core to center sump. This is called funnel flow and is illustrated in figures below.

Based on 8" unload auger



2 seconds

From time auger starts, you have 2 seconds to react.

4 seconds

In 4 seconds you are trapped

8 seconds

After 8 seconds, you are completely covered.

Grain across bottom and around sides of bin does not move. The speed at which grain is removed makes the funnel flow very dangerous. A person in a bin would be carried to center, quickly drawn under, and suffocated. An 8" auger can transfer 3,000 cubic feet of grain per hour (52 cubic feet per minute). A person about 6' tall displaces about 7-1/2 cubic feet, assuming an average body diameter of 15 inches. This means the entire body could be submerged in a funnel in about 8 seconds. Even more importantly, you could be up to your knees and totally helpless to free yourself in less than 4 seconds.

Grain surface may appear solid but not be. A small opening in unload gate gives entire surface the quality of quicksand. When a single kernel is removed from bottom of bin, kernels directly above it rush to fill the void. Flowing grain is fluid. Objects on surface sink and heavy objects sink faster than small ones.


Flowing grain is like water in that it will exert pressure over entire area of any object that is submerged in it. However, the amount of force required to pull someone up through grain is much greater than in water because grain exerts no buoyant force and has much greater internal friction.

Even if grain has stopped flowing, submerged objects or people are difficult to extract. Even victims with tremendous upper-body strength cannot pull themselves out if they are buried to the chest. The force required to remove someone buried below the surface of grain can easily exceed 2,000 pounds, which is about the same as needed to lift a small car.

If you become trapped in a bin of flowing grain with nothing to hold onto but you are still able to walk, stay near outside wall. Keep walking until bin is empty or grain flow stops. If you become covered in flowing grain, cup your hands over your mouth and take short breaths. This may keep you alive until help arrives. Additional personnel should call for an emergency rescue team or fire department immediately. Ventilate bin with an aeration system but **DO NOT** activate heat source. Wait for emergency crews to arrive before attempting rescue. Offer assistance to rescuers and follow directions given by incident commander.

Bridged & Caked Grain


Spoiled grain tends to clump together and grain that is stored in cold temperatures can appear to have a solid surface while, in reality, it may collapse if walked upon. Be aware of a potential engulfment hazard when walking on surface crust. Never enter a bin unless you know the nature of previous grain removal, especially if any crusting is evident. Proper safety precautions must be taken. **After grain has been removed, look for a funnel shape at surface of grain mass. If grain appears to be undisturbed, then it has bridged and created a cavity.**



SWCM0018
BRIDGED
102105BAP

Bridged grain may create air spaces in a partially unloaded bin (see above). As grain is removed from bin, a cavity develops under crusted surface. This situation presents several dangers. First, the person may break through the surface and be trapped instantly in flowing grain. Another danger is that a large void may be created under the bridge by previous unloading so that a person who breaks through crust may be buried under grain and suffocate, even without auger running. The third hazard is that if grain is wet enough to mold and bridge across bin, there may be little oxygen present in cavity due to microbial gases. A person falling into a cavity will be forced to breathe toxic gases, even though his head is above surrounding grain. From outside of bin, use a pole or other object to break bridge, causing it to collapse.

Grain can also cake in a large mass against wall when it has been stored improperly or in poor condition. Mass of grain can cause engulfment or crushing hazards to workers who attempt to break grain loose with shovels or other objects.



SWCM0018
COLLAPSE
102105BAP

This risk increases as capacity of bin increases. A person lying prone and covered by 1 foot of grain will be subjected to a force of over 300 lbs. Be alert while working with grain that has gone out of condition. Entering a bin when there may be molds, blocked flow, cavities, crusting, and possible cave-ins can cost you your life. When you are breaking up large masses of vertically crusted grain, do so with a long wooden pole from manhole above grain.

Moving Parts

When bin is nearly empty, sweep (floor) auger travels at a faster speed around bin. If caught in rotating auger, a body part can be pulled along with grain, cutting and tearing flesh. Also, an exposed auger in a sump can cause serious injury if sump is stepped into or fallen into. All shields should be in place to prevent body parts from getting caught.

To help prevent tragedy, **SAFETY SHOULD BE THE TOP PRIORITY**. Preparation is the first and most important step. Failure to follow precautions listed below may cause death or serious injury.



- Keep hands, feet and clothing away from moving parts. Loose clothing can become entangled in rotating parts and cause serious injury or death.
- Guards and shields are provided for your protection. Make sure all are secure and in place while machine is in operation.
- Replace safety shields that have been damaged or were removed for servicing equipment. Fasten shields securely.
- Be sure to wear tight-fitting clothing when working near a grain auger. Loose, floppy clothing, long shoestrings and drawstrings on hooded jackets can easily become entangled in rotating parts. Entangled clothing will pull the body into moving machinery and severe injury will result.
- Limit number of people around augers when in use. Only those who are essential to job should be there.
- Watch children closely. Never leave them unattended. Keep them away from vehicles, flowing grain and moving parts. Small hands and feet can penetrate even properly shielded augers, belts and PTOs. Teach children which areas are safe and which are not.
- Be certain all machinery is in good working condition.

Lockout/Tagout

Lockout/Tagout refers to specific practices and procedures to safeguard against unexpected energization or startup of machinery and equipment or release of hazardous energy during service or maintenance activities. This requires, in part, that an authorized individual isolate machinery or equipment from its energy source(s) before performing service or maintenance. It also requires authorized individual(s) to either lock or tag energy-isolating device(s) to prevent release of hazardous energy, and take steps to verify energy has been isolated effectively.

Grain storage structures and handling equipment may create hazardous work areas. Individuals should make sure they take proper steps to prevent injuries, illness or death. Be certain proper lockout/tagout procedures are followed before performing any service on equipment or entering bin.

Lockout refers to a device that uses a lock -- either key or combination type -- to hold an energy-isolating device in a safe position and prevent energizing of a machine or equipment. This device ensures that equipment being controlled cannot be operated until lockout device is removed. Tags must be used with all locking devices. Tags should be affixed in a manner that clearly identifies the individual servicing the equipment

Tagout refers to placement of a tag on a device that is not capable of being locked out, to indicate equipment may not be operated until tag device is removed. These tags are singularly identified with the individual applying the device and servicing the equipment. These tags **do not** provide physical restraint on those devices that require a restraint.

Owners/Operators are responsible for developing site-specific Lockout/Tagout procedures based on equipment, conditions and situations at their individual locations. OSHA's Lockout/Tagout procedures (29CFR 1910.147) can be obtained at www.osha.gov.

Ventilation

When entering an inadequately ventilated area, individuals may be at risk of being overcome by respiratory hazards (gases, fumes and dust) that can cause permanent lung damage or even death. Working in grain bins without proper respiratory protection increases a person's chance of developing a respiratory disease.



Owners/Operators are responsible for developing site-specific personal protective equipment standards. OSHA's personal protective equipment standards (29CFR 1910.134) can be obtained at www.osha.gov.

Sharp Edges & Obstacles



When working in, on or near a bin, remember that metal edges are sharp. To avoid injuries, wear protective clothing and handle equipment and parts with care. An excellent safety practice is to keep bin site clear of scrap iron and other foreign materials that may get covered up by snow or tall grass. Items or debris left near bin site may interfere with safe, unobstructed movement around bin.

Be aware of trucks, tractors, wagons, augers, hoppers and pits, etc. Never allow anyone to ride on trucks equipped with grain beds or gravity dump wagons. Keep children off grain vehicles and out of bins while loading and unloading. Always know where all family members are (especially children) at all times when grain is being loaded, unloaded, moved or otherwise handled.


Falls & Obstructions

Falls from grain bins at any height can cause injury. Ladders on bins can become very slippery or icy in inclement weather. Maintain a secure handhold and foothold when climbing on bin. Metal is slippery when wet. Never carry items while climbing on bins. Also, be certain no obstacles are in front of ladder.

Slippery metal, broken or loose ladder rungs and loose handholds can be very dangerous. Repair loose ladder rungs and handholds as soon as they are discovered. Follow maintenance guidelines listed at back of operation manual to prevent serious injury.

Make sure there are no obstructions near ladder rungs. Be certain wind rings (usually on taller commercial bins) are installed according to illustration at right so adequate clearances for hands and feet are provided. Wind rings must be a minimum of 1-1/2" below and 4-1/2" above any ladder rung. A wind ring assembled within 4-1/2" above a ladder rung can interfere with foothold and cause you to fall. Center of outside ladder must be at least 7" from sidewall.

NOTE: Failure to install ladder and safety cages correctly and to use fall restraint or arrest systems correctly may cause death or serious injury. Contact your dealer if proper ladder and accessories are not installed.



Ladder Safety

- Working load of ladder is 300 pounds. Do not overload.
- Inspect ladder carefully before use. Never climb deteriorated, damaged or improperly assembled ladder components.
- Never use ladder if you are physically impaired.
- Never carry items while climbing.
- Always have another person present while climbing.
- Use safety harness and safety line as required.
- Metal is slippery when wet. Always maintain a firm grip and wear slip-resistant shoes when climbing.
- Always face ladder when using it.
- Never apply external load. Never push or pull anything while on ladder.



WARNING: Failure to follow precautions above may result in death or serious injury.

Fall Restraints & Arrest Systems

When working at a height where fall hazards exist, always use a fall restraint or fall arrest system. Inspect components before each use for wear, damage and other deterioration. Remove defective components from service according to manufacturer's instructions. Failure to heed this warning may cause death or serious injury.

A **fall restraint system** consists of a body belt or harness, lanyard and anchor. The system is arranged so the individual is prevented from falling. Fall restraint systems should be used in accordance with manufacturer's recommendations and instructions.

A **fall arrest system** consists of a harness, lanyard and anchor. The system stops a fall within specified parameters. Fall arrest systems should be used in accordance with manufacturer's recommendations and instructions.

Lifelines and safety harnesses are used with both systems. A **lifeline** is a component consisting of a flexible line (rope or cable) for connection to an anchorage at one end to hang vertically (vertical lifeline), or for connection to anchorages at both ends to stretch horizontally (horizontal lifeline). Lifelines also serve as a means for connecting other components of a fall protection system. A **safety harness** has straps that wrap around an individual in a manner that will distribute the fall arrest forces over thighs, pelvis, waist, chest, and shoulders with a means of attaching it to other components of a fall protection system. Follow manufacturer's instructions when using a lifeline and safety harness.



Individuals who enter a grain storage structure from a level at or above stored grain should be equipped with a lifeline and harness. When entering any bin or storage unit, have multiple people outside and one inside. A single person cannot go for help and give first aid simultaneously.

Connections outside bin on roof should be made to peak ring. Lifelines should not let individual extend past eave of roof. If work needs to be done on portions of sidewall, proper equipment such as lifts or cranes should be used. When working inside bin, appropriate connections should be made to rafters, peak ring or sidewall.


NOTE: Fall-protection equipment used with bin ladder(s) will depend on whether federal Occupational Safety and Health Administration rules apply to bin site. If ladder is 24' tall or taller and bin is on an OSHA-defined commercial site (11 or more full-time employees), fall-arrest cable system or B-Option ladders, safety cages & platforms package must be used. On sites where OSHA rules do not apply, standard (S-Option) Sukup ladders package can be used. See Ladders, Safety Cages & Platforms section in bin erection manual. Maximum distance between platforms in B-Option package is 22'. Maximum distance between platforms in S-Option package is 30'.

DISCLAIMER: It shall be the sole responsibility of the customer to determine applicability of OSHA fall protection rules at bin site. Sukup Manufacturing Co. will not be responsible for any personal injury or loss resulting from failure to comply or from incorrect installation or use of fall protection equipment.

Restraint Anchor & Knot-Passing Pulley


A **Restraint anchor** eyebolt capable of supporting 1,000 lbs. and a **knot-passing pulley** are provided for use in ALL Sukup bins. Restraint anchor, pulley, feeder line and decals must be field-installed. See instructions in Bin Construction Manual.

Pulley is intended to be used with a lifeline and safety harness (neither supplied by Sukup Manufacturing Co.). A feeder line should pass through pulley and through restraint anchor at eave of bin near manhole. Feeder line is used to pull lifeline through knot-passing pulley for safety harness attachment. Do not attach safety harness to feeder line. Use safety equipment according to manufacturers' instructions. Refer to Fall Restraints & Arrest Systems section and to www.osha.gov for additional safety information.




Attaching J08621 eyebolt & stickers L0907 & L09073

Drawing above shows eyebolt and sticker locations. Drawings below show pulley installation depending on roof type/rating.



Top Causes of Bin Failure

- **OFF-CENTER (ECCENTRIC) UNLOADING AND/OR LOADING**
- Grain that does not flow freely (spoiled, frozen, crusted etc.)
- Inner door panels not tightly secured to inner door frame
- Augers, spouts or conveyors improperly attached to roof
- Sidedraw improperly installed or operated
- Rusted wall sheets
- Simultaneous loading and unloading
- Settling of foundation (uneven pad)
- Improper usage (storage and aeration)
- Storing wet and dry grain in the same bin without stirring
- Neglect of bin maintenance
- Modifications made during installation or assembly
- Incorrectly installed sidewall sheets and/or stiffeners
- Blocked roof vents causing excessive pressures on roof (overfilling, frosted vents, etc.)
- Improper temperature cable support and/or placement



SWOM0030
9/3/2011BAP



WARNING: Damage from issues listed above may cause sudden structural failure and collapse, which may result in death or serious injury. Frequently monitor and inspect bin and foundation for any deflections, cracks or deviations that may occur. Follow operation and maintenance instructions described in this manual.

Determining an Existing Bin's Fitness for Duty

Farm and commercial bins are built to last for many years. However, factors such as weather, usage, accidents and seismic activity can put stresses on a bin that compromise its structural fitness. Following are issues to consider in determining whether a bin should be taken out of service and/or replaced.

- Extensive rust on inside or outside of roof and/or sidewall sheets, or on stiffeners
- Rust holes or significant wearing and/or tearing of roof and/or sidewall sheets
- Damaged stiffeners or sidewall sheets (kinked or bent from off-center loading or unloading, etc.)
- Leaking roof or sidewalls
- Missing connections between wall and roof structure
- Missing or sheared bolts
- Loose, broken or shifted anchors
- Damaged foundation or bin floor (cracks in concrete foundation, uneven settlement)

Minor levels of any of these issues should be repaired promptly. If levels are moderate to high, bin should be taken out of service or replaced. If unsure, take pictures of the issues and contact an independent consulting engineer.


Besides condition of bin, other factors to consider in determining whether to decommission it include age of bin, insurability, capacity, compatibility with modern grain handling and moving equipment, and future plans for bin site.

Construction Safety

On grain bin construction sites, carelessness and/or operator error may result in serious injury or death. Hazard control and accident prevention depend on awareness, cautiousness, and proper training of personnel involved in construction of bin. Be certain all crew members are properly trained and thoroughly familiar with all aspects of grain bin construction.

Listed below are items construction crew members should be knowledgeable of to minimize risk of injury to personnel and damage to equipment. **NOTE:** Following items are examples taken from a broad list of OSHA's Safety and Health Regulations for Construction. Generally, these are common requirements/items necessary on grain bin construction sites.

- **Personal Protective**
 - Head Protection
 - Hearing Protection
 - Eye and Face Protection
 - Steel Toed Boots/Shoes
 - Gloves
- **Concrete Construction**
- **Material Handling & Storage**
- **Tools – Hand and Power**
- **Welding and Cutting**
- **Electrical**
- **Ladders**
- **Scaffolds and Working Platforms**
- **Fall Protection**
- **Steel Erection**
 - Center Pole (Roof) Jack*
 - Sidewall Jacks*
- **Motorized Equipment**
 - Trenchers
 - Forklifts
 - Skidsteers
 - Telehandlers
 - Boom Lifts
- **Cranes and Hoists**
- **Signs and Signals for Use of Motorized Equipment**



***NOTE:** Be certain to read and fully understand correct operating procedures for bin jacking equipment. Bin jack users must be thoroughly familiar with proper usage techniques. Jack manufacturers will assume no responsibility for damage to equipment or any injury resulting from operation of their equipment.

Erectors/contractors are responsible for developing site-specific construction guidelines and procedures based on equipment, conditions and situations at their individual location. OSHA's Safety and Health Regulations for Construction (29CFR1926) can be obtained at www.osha.gov.

Foundation Recommendations for Sukup Grain Bins

Site Selection

When selecting a site for grain storage and handling, many factors need to be considered. Site must allow convenient access for loading, unloading and related work if site is to become a grain system center.


Site should have soil that is firm, level and free of vegetation and underlying debris. Any added fill should be thoroughly compacted to prevent uneven settlement from bin weight.

Locations of handling equipment, fans, heaters, ladders and stairways, etc., must be predetermined. Future expansion should be factored into site selection process, and careful consideration must be paid to access to electrical and gas lines, and to maintaining safe distances from power supply sources.

Electrical Clearances

Check with local electric utility for assistance in planning a safe grain storage and handling site. State codes may vary on clearances. To prevent overhead electrical safety issues, bury electrical lines.

American National Standards Institute (ANSI) provides safety recommendations for grain bins in ANSI C2 2017. "National Electric Safety Code" Rule 234F Figs. 1 and 2 show clearances for bins and grain handling equipment.



V_1 = Vertical clearance above a building

V_2 = Vertical clearance above land

T = Transition clearance

Fig. 1 – Clearances for grain bins filled by permanently installed augers, conveyers or elevators. (ANSI C2 2017)





Fig. 2 -- Clearances for grain bins filled by portable augers, conveyors or elevators. (ANSI C2 2017)



Accessory Location

It is important that all components of grain bin be located properly to maximize efficiency and effectiveness of equipment. Most factors should be considered before foundation is poured. Double-check desired location of roof manhole, sidewall and roof ladders, eave platform(s), and walkway(s). Below is a typical layout.




Fig. 3 – Suggested layout of bin components

Foundation Preparation Recommendations

DISCLAIMER: Sukup Manufacturing Co. assumes no responsibility regarding the foundation specifications. This is not an engineered foundation and shall not be constructed as such. The specifications given are intended for quoting and estimating purposes only. It shall be the sole responsibility of the customer to obtain actual foundation drawings designed by and constructed to the specifications of a licensed professional structural engineer with knowledge of the actual soil and load specific to the project and location. Consideration should also include, but not be limited to, live loads, dead loads, wind loads, soil bearing loads, seismic zone, proper moisture run-off on top of base, and types of aeration applied for the project.

Sukup Manufacturing Co. will not be responsible for any damage to a product, including, but not limited to, any damage that results from poor soil conditions or inadequate concrete type, grade, bearing strength, and construction method. Soil bearing tests must be performed by a competent, independent, engineering firm. Concrete foundation construction must be done by a competent concrete contractor.

Check local and/or regional building codes and regulations to ensure compliance.

Sukup Manufacturing Co. provides foundation data based on 3,000 psf bearing capacity.

All backfill material used in foundation preparations should be clean, crushed stone or sand/gravel mixture of a highly compactable material. Backfill should be layered up in 6" lifts and well compacted.

Concrete Specifications

Cement is to be Type 1 Portland Cement that conforms to ASTM C150.

Maximum aggregate size is to be 3/4 of minimum clear spacing between reinforcing bars and/or wire mesh.

Concrete must be 3,000 psi compressive strength at 28 days cured minimum.

Concrete is to be cured at 50°F and kept moist for a minimum of seven (7) days.

Foundation surface should not vary from level by more than 1/4" in 10 feet or more than 1/4" from specified elevation. Uneven surface may cause bin failure.

Elevation of surface above grade should not exceed 6".

A beveled edge around foundation allows water to run off of surface.

Reinforcing Steel

Steel reinforcing bar (rebar) should conform to ASTM A615 or ASTM A617 and be Grade 60 or better.

To properly size diameter of rebar for specific bin size, consult bin specifications chart.

All circumferential bar laps should be 35 bar diameters and staggered by 3' minimum.


All laps of circumferential bar (rebar) should be bound by either wire tie or welded. Number 6 (6" x 6") wire mesh may be used. Overlap of wire mesh should be 6 inches minimum.

Anchor Bolts


Follow specifications on subsequent pages for appropriate size foundation and anchor bolts.

Foundation Construction Procedure (Monolithic Type)

1. Determine center of foundation. Set a center stake. It can be anything from a simple 2" x 4" to a solid steel stake. In any case, a pivot point must be established from which outside radius can be marked.
2. Attach a straight 2" x 4" board or steel tube to center stake. Attachment must be two feet longer than radius of bin. Adjust so bottom of board is same as desired height of floor surface. Attach so device can swivel 360 degrees unobstructed and remain at desired height. **TIP:** Use a stout enough device that can be used as a concrete leveler later when concrete is poured. See Fig. 4.




3. Determine radius of bin from center stake and mark on board or steel tube. Attach a second pointed stake to board so it can be used to scribe radius of bin foundation. See Fig. 5.



4. Dig footings for foundation per specifications given in foundation chart.

5. Place backfill using 6" lifts. Compact well. Board can be used to level backfill. Measure from bottom of board to determine proper thickness of floor, as specified.
6. Set forms, ensuring they are level and sturdy.
7. Lay steel rebar laterally into footings as specified. Follow overlap procedures outlined in **Reinforcing Steel** guidelines.
8. Lay steel wire mesh in floor area if specified.
9. Lay steel rebar radially in floor area if specified.
10. Wet sand/gravel and pour concrete.
11. Anchor bolts can be placed into concrete when concrete is wet or after concrete has cured. For wet concrete installation, follow instructions 12 through 14. Otherwise skip to 15.
12. Consult foundation specifications table for anchor bolt placement and chord dimensions.



13. Using center stake and scribe board, scribe anchor bolt radius into wet concrete. See Fig. 6.
14. Place foundation anchor bolts into concrete while concrete is workable.
15. Anchor bolts may be placed after concrete has cured by drilling holes on concrete and placing bolts with an anchoring adhesive material such as epoxy. Epoxy adhesive should comply with ASTM C881, two-component material suitable for use on dry and damp surfaces. All surfaces must be clean, dry and free of all dust and debris. Clearly mark all areas to be anchored. Drill holes in concrete and inject epoxy adhesive according to manufacturer's specifications. Insert anchor bolt fully into hole and remove excess adhesive. Rebar or plate cutters may be used accordingly when rebar is in the way. Inspect all anchor locations after adhesive has cured.




Fig. 7




Fig. 8

Farm Stiffened Foundation Specifications – Monolithic
3000 psf Soil Bearing Capacity

Model	Nom. Bin Diam.	Concrete		Anchor						6" Above Grade					
		Diameter	Radius	Radius	Chord	Total	T	D	W	Footing Rebar					
										Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Qty	Size	Lin Ft
1503	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	5	221	3	2	4	100
1504	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	5	221	3	2	4	100
1505	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	5	221	3	2	4	100
1506	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	5	221	3	2	4	100
1507	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	5	221	3	2	4	100
1508	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	6	221	3	2	4	100
1509	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	6	221	3	2	5	102
1510	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	7	221	2	2	5	102
1511	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	7	221	2	3	4	150
1512	15'	16' 7 1/8"	8' 3 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	30"	8	221	2	3	4	150
1803	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	7	312	4	2	4	119
1804	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	7	312	4	2	4	119
1805	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	7	312	4	2	4	119
1806	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	7	312	4	2	4	119
1807	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	8.5	312	3	2	4	119
1808	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	8.5	312	3	2	4	119
1809	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	8.5	312	3	2	5	120
1810	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	9.5	312	3	2	5	120
1811	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	9.5	312	3	3	4	178
1812	18'	19' 7"	9' 9 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	30"	10.5	312	3	3	4	178
2103	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	9.5	418	5	2	4	140
2104	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	9.5	418	5	2	4	140
2105	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	9.5	418	5	2	4	140
2106	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	9.5	418	5	2	4	140
2107	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	10.5	418	5	2	4	140
2108	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	10.5	418	5	2	5	142
2109	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	10.5	418	5	2	5	142
2110	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	24"	12	418	4	3	4	208
2111	21'	22' 6"	11' 3"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	13	418	4	3	4	208
2112	21'	22' 8"	11' 4"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	13	418	4	3	4	208
2403	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	11.5	540	7	2	4	157
2404	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	11.5	540	7	2	4	157
2405	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	11.5	540	7	2	4	157
2406	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	11.5	540	7	2	4	157
2407	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	13	540	6	2	5	159
2408	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	13	540	6	2	5	159
2409	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	24"	15	540	6	2	5	159
2410	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	24"	15	540	6	3	4	224
2411	24'	25' 6"	12' 9"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	30"	16.5	540	6	3	4	224
2412	24'	25' 8"	12' 10"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	36"	18	540	6	3	5	227
2703	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	14.5	677	8	2	4	179
2704	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	14.5	677	8	2	4	179
2705	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	14.5	677	8	2	4	179
2706	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	14.5	677	8	2	4	179
2707	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	16	677	8	2	5	182
2708	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	16	677	8	2	5	182
2709	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	18	677	8	2	5	182
2710	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	18	677	7	3	5	270
2711	27'	28' 6"	14' 3"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	30"	19.5	677	7	3	5	270
2712	27'	28' 8"	14' 4"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	36"	21	677	7	3	5	270
3003	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	17	830	10	2	4	197
3004	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	17	830	10	2	4	197
3005	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	17	830	10	2	4	197
3006	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	17	830	10	2	4	197
3007	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	19	830	10	2	5	200
3008	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	19	830	10	2	5	200
3009	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	24"	21	830	10	2	5	200
3010	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	6"	12"	30"	23	830	9	3	5	300
3011	30'	31' 6"	15' 9"	15' 2 1/8"	4' 9"	20	6"	12"	30"	23	830	9	3	5	300
3012	30'	31' 8"	15' 10"	15' 2 1/8"	4' 9"	20	6"	12"	36"	25	830	9	3	5	300

Model	Nom. Bin Diam.	Concrete		Anchor			6" Above Grade									
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			
													Qty	Size	Lin Ft	
3303	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	20	998	13	2	5	222	
3304	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	20	998	13	2	5	222	
3305	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	20	998	13	2	5	222	
3306	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	20	998	13	2	5	222	
3307	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	18"	22.5	998	12	2	6	225	
3308	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	18"	22.5	998	12	2	6	225	
3309	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	24"	24.5	998	12	2	6	225	
3310	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	6"	12"	30"	27	998	11	3	5	330	
3311	33'	34' 6"	17' 3"	16' 8"	4' 8 15/16"	22	6"	12"	30"	27	998	11	3	5	330	
3312	33'	34' 8"	17' 4"	16' 8"	4' 8 15/16"	22	6"	12"	36"	29	998	11	3	5	330	
3603	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	24	1182	15	2	5	240	
3604	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	24	1182	15	2	5	240	
3605	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	24	1182	15	2	5	240	
3606	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	24	1182	15	2	5	240	
3607	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	18"	26	1182	14	2	6	243	
3608	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	28	1182	14	2	6	243	
3609	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	28	1182	14	2	6	243	
3610	36'	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	30"	31	1182	13	3	5	355	
3611	36'	37' 6"	18' 9"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	36"	33	1182	13	3	5	355	
3612	36'	37' 8"	18' 10"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	36"	33	1182	13	3	6	358	
4203	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	31	1597	21	2	5	280	
4204	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	31	1597	21	2	5	280	
4205	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	31	1597	21	2	5	280	
4206	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	34	1597	20	2	6	283	
4207	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	34	1597	20	2	6	283	
4208	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	24"	37	1597	19	3	5	415	
4209	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	24"	37	1597	19	3	5	415	
4210	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	30"	40	1597	19	3	5	415	
4211	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	36"	43	1597	19	3	6	418	
4212	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	18"	42"	53	1597	18	3	6	418	
4803	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	40	2074	27	2	5	320	
4804	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	40	2074	27	2	5	320	
4805	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	40	2074	27	2	5	320	
4806	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	43.5	2074	26	2	6	324	
4807	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	43.5	2074	26	2	6	324	
4808	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	24"	46	2074	25	3	5	480	
4809	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	30"	49	2074	25	3	5	480	
4810	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	30"	49	2074	25	3	5	480	
4811	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	36"	53	2074	24	3	6	486	
4812	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	18"	42"	65	2074	24	3	6	486	

Model	Nom. Bin Diam.	Concrete		Anchor			18" Above Grade											
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			Vert Rebar (24"L)		
													Qty	Size	Lin Ft	Qty	Size	Lin Ft
1503	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	7	221	3	4	4	200	32	4	64
1504	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	7	221	3	4	4	200	32	4	64
1505	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	7	221	3	4	4	200	32	4	64
1506	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	7	221	3	4	4	200	32	4	64
1507	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	7	221	3	4	4	200	32	4	64
1508	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	8.5	221	3	4	4	200	32	4	64
1509	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	8.5	221	3	4	5	204	32	4	64
1510	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	10	221	2	4	5	204	32	4	64
1511	15'	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	10	221	2	6	4	300	32	4	64
1512	15'	16' 7 1/8"	8' 3 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	30"	11.5	221	2	6	4	300	32	4	64

Model	Nom. Bin Diam.	Concrete		Anchor			18" Above Grade											
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			Vert Rebar (24"L)		
													Qty	Size	Lin Ft	Qty	Size	Lin Ft
1803	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	8.8	312	4	4	4	238	38	4	76
1804	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	8.8	312	4	4	4	238	38	4	76
1805	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	8.8	312	4	4	4	238	38	4	76
1806	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	8.8	312	4	4	4	238	38	4	76
1807	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	11	312	3	4	4	238	38	4	76
1808	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	11	312	3	4	4	238	38	4	76
1809	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	11	312	3	4	5	240	38	4	76
1810	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	13	312	3	4	5	240	38	4	76
1811	18'	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	13	312	3	6	4	356	38	4	76
1812	18'	19' 7"	9' 9 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	30"	16.5	312	3	6	4	356	38	4	76
2103	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	11.5	418	5	4	4	280	44	4	88
2104	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	11.5	418	5	4	4	280	44	4	88
2105	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	11.5	418	5	4	4	280	44	4	88
2106	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	11.5	418	5	4	4	280	44	4	88
2107	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	13.5	418	5	4	4	280	44	4	88
2108	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	13.5	418	5	4	5	284	44	4	88
2109	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	13.5	418	5	4	5	284	44	4	88
2110	21'	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	24"	17	418	4	6	4	416	44	4	88
2111	21'	22' 6"	11' 3"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	19	418	4	6	4	416	44	4	88
2112	21'	22' 8"	11' 4"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	19	418	4	6	4	416	44	4	88
2403	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	14	540	7	4	4	314	50	4	100
2404	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	14	540	7	4	4	314	50	4	100
2405	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	14	540	7	4	4	314	50	4	100
2406	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	14	540	7	4	4	314	50	4	100
2407	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	17	540	6	4	5	318	50	4	100
2408	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	17	540	6	4	5	318	50	4	100
2409	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	24"	20	540	6	4	5	318	50	4	100
2410	24'	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	24"	20	540	6	6	4	448	50	4	100
2411	24'	25' 6"	12' 9"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	30"	23	540	6	6	4	448	50	4	100
2412	24'	25' 8"	12' 10"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	36"	26	540	6	6	5	454	50	4	100
2703	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	17	677	8	4	4	358	57	4	114
2704	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	17	677	8	4	4	358	57	4	114
2705	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	17	677	8	4	4	358	57	4	114
2706	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	17	677	8	4	4	358	57	4	114
2707	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	20	677	8	4	5	364	57	4	114
2708	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	20	677	8	4	5	364	57	4	114
2709	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	23	677	8	4	5	364	57	4	114
2710	27'	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	23	677	7	6	5	540	57	4	114
2711	27'	28' 6"	14' 3"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	30"	27	677	7	6	5	540	57	4	114
2712	27'	28' 8"	14' 4"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	36"	31	677	7	6	5	540	57	4	114
3003	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	21	830	10	4	4	394	63	4	126
3004	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	21	830	10	4	4	394	63	4	126
3005	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	21	830	10	4	4	394	63	4	126
3006	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	21	830	10	4	4	394	63	4	126
3007	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	24.5	830	10	4	5	400	63	4	126
3008	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	24.5	830	10	4	5	400	63	4	126
3009	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	24"	28.5	830	10	4	5	400	63	4	126
3010	30'	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	6"	12"	30"	31.5	830	9	6	5	600	63	4	126
3011	30'	31' 6"	15' 9"	15' 2 1/8"	4' 9"	20	6"	12"	30"	31.5	830	9	6	5	600	63	4	126
3012	30'	31' 8"	15' 10"	15' 2 1/8"	4' 9"	20	6"	12"	36"	36	830	9	6	5	600	63	4	126
3303	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	24.5	998	13	4	5	444	69	4	138
3304	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	24.5	998	13	4	5	444	69	4	138
3305	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	24.5	998	13	4	5	444	69	4	138
3306	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	24.5	998	13	4	5	444	69	4	138
3307	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	18"	28	998	12	4	6	450	69	4	138
3308	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	18"	28	998	12	4	6	450	69	4	138
3309	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	24"	32.5	998	12	4	6	450	69	4	138
3310	33'	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	6"	12"	30"	36	998	11	6	5	660	69	4	138
3311	33'	34' 6"	17' 3"	16' 8"	4' 8 15/16"	22	6"	12"	30"	36	998	11	6	5	660	69	4	138
3312	33'	34' 8"	17' 4"	16' 8"	4' 8 15/16"	22	6"	12"	36"	39.5	998	11	6	5	660	69	4	138

Model	Nom. Bin Diam.	Concrete		Anchor					18" Above Grade									
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			Vert Rebar (24"L)		
													Qty	Size	Lin Ft	Qty	Size	Lin Ft
3603	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	28	1182	15	4	5	480	75	4	150
3604	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	28	1182	15	4	5	480	75	4	150
3605	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	28	1182	15	4	5	480	75	4	150
3606	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	28	1182	15	4	5	480	75	4	150
3607	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	18"	32.5	1182	14	4	6	486	75	4	150
3608	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	36.5	1182	14	4	6	486	75	4	150
3609	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	36.5	1182	14	4	6	486	75	4	150
3610	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	30"	41.5	1182	13	6	5	710	75	4	150
3611	36"	37' 6"	18' 9"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	36"	45	1182	13	6	5	710	75	4	150
3612	36"	37' 8"	18' 10"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	36"	45	1182	13	6	6	716	75	4	150
4203	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	36.5	1597	21	4	5	540	88	4	176
4204	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	36.5	1597	21	4	5	540	88	4	176
4205	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	36.5	1597	21	4	5	540	88	4	176
4206	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	41.5	1597	20	4	6	566	88	4	176
4207	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	41.5	1597	20	4	6	566	88	4	176
4208	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	24"	46.5	1597	19	6	5	830	88	4	176
4209	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	24"	46.5	1597	19	6	5	830	88	4	176
4210	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	30"	51	1597	19	6	5	830	88	4	176
4211	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	36"	57	1597	19	6	6	836	88	4	176
4212	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	18"	42"	70.5	1597	18	6	6	836	88	4	176
4803	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	46	2074	27	4	5	640	100	4	200
4804	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	46	2074	27	4	5	640	100	4	200
4805	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	46	2074	27	4	5	640	100	4	200
4806	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	51.5	2074	26	4	6	648	100	4	200
4807	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	51.5	2074	26	4	6	648	100	4	200
4808	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	24"	57.5	2074	25	6	5	960	100	4	200
4809	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	30"	63.5	2074	25	6	5	960	100	4	200
4810	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	30"	63.5	2074	25	6	5	960	100	4	200
4811	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	36"	69	2074	24	6	6	972	100	4	200
4812	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	18"	42"	85.5	2074	24	6	6	972	100	4	200

Model	Nom. Bin Diam.	Concrete		Anchor					24" Above Grade									
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			Vert Rebar (30"L)		
													Qty	Size	Lin Ft	Qty	Size	Lin Ft
1503	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	8	221	3	4	4	200	32	4	80
1504	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	8	221	3	4	4	200	32	4	80
1505	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	8	221	3	4	4	200	32	4	80
1506	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	8	221	3	4	4	200	32	4	80
1507	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	12"	8	221	3	4	4	200	32	4	80
1508	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	10	221	3	4	4	200	32	4	80
1509	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5"	12"	18"	10	221	3	4	5	204	32	4	80
1510	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	12	221	2	4	5	204	32	4	80
1511	15"	16' 5 1/8"	8' 2 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	24"	12	221	2	6	4	300	32	4	80
1512	15"	16' 7 1/8"	8' 3 9/16"	7' 8 19/32"	4' 9 7/32"	10	5.5"	12"	30"	14	221	2	6	4	300	32	4	80
1803	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	10	312	4	4	4	238	38	4	95
1804	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	10	312	4	4	4	238	38	4	95
1805	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	10	312	4	4	4	238	38	4	95
1806	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	12"	10	312	4	4	4	238	38	4	95
1807	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	13	312	3	4	4	238	38	4	95
1808	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	13	312	3	4	4	238	38	4	95
1809	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5"	12"	18"	13	312	3	4	5	240	38	4	95
1810	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	15.5	312	3	4	5	240	38	4	95
1811	18"	19' 5"	9' 8 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	24"	15.5	312	3	6	4	356	38	4	95
1812	18"	19' 7"	9' 9 1/2"	9' 2 1/2"	4' 9 3/16"	12	5.5"	12"	30"	18.5	312	3	6	4	356	38	4	95
2103	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	13	418	5	4	4	280	44	4	110
2104	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	13	418	5	4	4	280	44	4	110
2105	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	13	418	5	4	4	280	44	4	110
2106	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	12"	13	418	5	4	4	280	44	4	110
2107	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	16	418	5	4	4	280	44	4	110
2108	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	16	418	5	4	5	284	44	4	110
2109	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5"	12"	18"	16	418	5	4	5	284	44	4	110
2110	21"	22' 5"	11' 2 1/2"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	24"	19	418	4	6	4	416	44	4	110
2111	21"	22' 6"	11' 3"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	22	418	4	6	4	416	44	4	110
2112	21"	22' 8"	11' 4"	10' 8 3/8"	4' 9 1/8"	14	5.5"	12"	30"	22	418	4	6	4	416	44	4	110

Model	Nom. Bin Diam.	Concrete		Anchor					24" Above Grade									
		Diameter	Radius	Radius	Chord	Total	T	D	W	Concrete cu yds	Wire Mesh sq ft	Fill Sand cu yds	Footing Rebar			Vert Rebar (30"L)		
													Qty	Size	Lin Ft	Qty	Size	Lin Ft
2403	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	15.5	540	7	4	4	314	50	4	125
2404	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	15.5	540	7	4	4	314	50	4	125
2405	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	15.5	540	7	4	4	314	50	4	125
2406	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	12"	15.5	540	7	4	4	314	50	4	125
2407	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	19.5	540	6	4	5	318	50	4	125
2408	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	18"	19.5	540	6	4	5	318	50	4	125
2409	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5"	12"	24"	22.5	540	6	4	5	318	50	4	125
2410	24"	25' 4"	12' 8"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	24"	22.5	540	6	6	4	448	50	4	125
2411	24"	25' 6"	12' 9"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	30"	26	540	6	6	4	448	50	4	125
2412	24"	25' 8"	12' 10"	12' 2 5/16"	4' 9 1/16"	16	5.5"	12"	36"	29.5	540	6	6	5	454	50	4	125
2703	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	18.5	677	8	4	4	358	57	4	142.5
2704	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	18.5	677	8	4	4	358	57	4	142.5
2705	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	18.5	677	8	4	4	358	57	4	142.5
2706	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5"	12"	12"	18.5	677	8	4	4	358	57	4	142.5
2707	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	22.5	677	8	4	5	364	57	4	142.5
2708	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	18"	22.5	677	8	4	5	364	57	4	142.5
2709	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	26.5	677	8	4	5	364	57	4	142.5
2710	27"	28' 4"	14' 2"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	24"	26.5	677	7	6	5	540	57	4	142.5
2711	27"	28' 6"	14' 3"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	30"	31	677	7	6	5	540	57	4	142.5
2712	27"	28' 8"	14' 4"	13' 8 3/16"	4' 9 1/16"	18	5.5"	12"	36"	35	677	7	6	5	540	57	4	142.5
3003	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	23	830	10	4	4	394	63	4	157.5
3004	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	23	830	10	4	4	394	63	4	157.5
3005	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	23	830	10	4	4	394	63	4	157.5
3006	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5"	12"	12"	23	830	10	4	4	394	63	4	157.5
3007	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	27.5	830	10	4	5	400	63	4	157.5
3008	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	18"	27.5	830	10	4	5	400	63	4	157.5
3009	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	5.5"	12"	24"	31.5	830	10	4	5	400	63	4	157.5
3010	30"	31' 4"	15' 8"	15' 2 1/8"	4' 9"	20	6"	12"	30"	36	830	9	6	5	600	63	4	157.5
3011	30"	31' 6"	15' 9"	15' 2 1/8"	4' 9"	20	6"	12"	30"	36	830	9	6	5	600	63	4	157.5
3012	30"	31' 8"	15' 10"	15' 2 1/8"	4' 9"	20	6"	12"	36"	40	830	9	6	5	600	63	4	157.5
3303	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	26.5	998	13	4	5	444	69	4	172.5
3304	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	26.5	998	13	4	5	444	69	4	172.5
3305	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	26.5	998	13	4	5	444	69	4	172.5
3306	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5"	12"	12"	26.5	998	13	4	5	444	69	4	172.5
3307	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	18"	31.5	998	12	4	6	450	69	4	172.5
3308	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	24"	36	998	12	4	6	450	69	4	172.5
3309	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	5.5"	12"	24"	36	998	12	4	6	450	69	4	172.5
3310	33"	34' 4"	17' 2"	16' 8"	4' 8 15/16"	22	6"	12"	30"	41	998	11	6	5	660	69	4	172.5
3311	33"	34' 6"	17' 3"	16' 8"	4' 8 15/16"	22	6"	12"	36"	46	998	11	6	5	660	69	4	172.5
3312	33"	34' 8"	17' 4"	16' 8"	4' 8 15/16"	22	6"	12"	36"	46	998	11	6	5	660	69	4	172.5
3603	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	30	1182	15	4	5	480	75	4	187.5
3604	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	30	1182	15	4	5	480	75	4	187.5
3605	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	12"	30	1182	15	4	5	480	75	4	187.5
3606	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5"	12"	18"	35.5	1182	15	4	5	480	75	4	187.5
3607	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	18"	35.5	1182	14	4	6	486	75	4	187.5
3608	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	41.5	1182	14	4	6	486	75	4	187.5
3609	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	5.5"	12"	24"	41.5	1182	14	4	6	486	75	4	187.5
3610	36"	37' 4"	18' 8"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	30"	46.5	1182	13	6	5	710	75	4	187.5
3611	36"	37' 6"	18' 9"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	36"	52.5	1182	13	6	5	710	75	4	187.5
3612	36"	37' 8"	18' 10"	18' 1 15/16"	4' 8 7/8"	24	6"	12"	42"	62	1182	13	6	6	716	75	4	187.5
4203	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	39.5	1597	21	4	5	540	88	4	220
4204	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	39.5	1597	21	4	5	540	88	4	220
4205	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	12"	39.5	1597	21	4	5	540	88	4	220
4206	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	45.5	1597	20	4	6	566	88	4	220
4207	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	5.5"	12"	18"	45.5	1597	20	4	6	566	88	4	220
4208	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	24"	51.5	1597	19	6	5	830	88	4	220
4209	42"	43' 3"	21' 7 1/2"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	30"	58.5	1597	19	6	5	830	88	4	220
4210	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	30"	58.5	1597	19	6	5	830	88	4	220
4211	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	12"	36"	64.5	1597	19	6	6	836	88	4	220
4212	42"	44' 3"	22' 1 7/16"	21' 1 3/4"	4' 8 13/16"	28	6"	18"	42"	78	1597	18	6	6	836	88	4	220
4803	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	48.5	2074	27	4	5	640	100	4	250
4804	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	12"	48.5	2074	27	4	5	640	100	4	250
4805	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	56	2074	27	4	5	640	100	4	250
4806	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	18"	56	2074	26	4	6	648	100	4	250
4807	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	24"	63	2074	26	4	6	648	100	4	250
4808	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	24"	63	2074	25	6	5	960	100	4	250
4809	48"	49' 3"	24' 7 1/2"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	30"	70.8	2074	25	6	5	960	100	4	250
4810	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	36"	78	2074	25	6	5	960	100	4	250
4811	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	12"	42"	84.5	2074	24	6	6	972	100	4	250
4812	48"	50' 2 7/16"	25' 1 7/32"	24' 1 1/2"	4' 8 3/4"	32	6"	18"	48"	103	2074	24	6	6	972	100	4	250

Placing Anchor Bolts

Use coordinates provided and GPS device to determine anchor locations. If unavailable, follow steps below.

STEP 1: Find anchor radius based on diameter of bin being built (Anchor radius is noted to left of Anchor Placement drawing).

STEP 2: Scribe anchor radius into concrete.


STEP 3: Determine where origin point will be. Have one person hold tape measure there. Have other person hold tape measure at distances shown at left of Anchor Placement drawing. Mark spots on radius – A, B, C, etc. – for anchor points. **NOTE:** Not all anchor points will be used for anchors. Repeat this step on other side until all anchor points are marked on radius.

STEP 4: Working counterclockwise from origin point, place an anchor at every other marked point, as shown on left side of drawing (B, D, etc.).

15' DIAMETER
ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 9 7/32"
B	9' 27/32"
C	12' 5 13/16"
D	14' 8 1/8"
E	15' 5 3/16"

CONCRETE RADIUS: See Chart
ANCHOR RADIUS: 7' 8 19/32"
BIN RADIUS: 7' 5 1/2"




SWB0121
060823 EAB

18' DIAMETER
ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 9 3/16"
B	9' 2 1/2"
C	13' 1/4"
D	15' 11 3/8"
E	17' 9 1/2"
F	18' 5"

CONCRETE RADIUS: See Chart
ANCHOR RADIUS: 9' 2 1/2"
BIN RADIUS: 8' 11 7/16"




SWB0066
060823 EAB

21' DIAMETER ANCHOR PLACEMENT

POINT DISTANCE

A	4' 9 1/8"
B	9' 3 3/8"
C	13' 4 1/16"
D	16' 8 3/4"
E	19' 3 5/16"
F	20' 10 5/16"
G	21' 4 3/4"

CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 10' 8 3/8"
 BIN RADIUS: 10' 5 5/16"




24' DIAMETER ANCHOR PLACEMENT

POINT DISTANCE

A	4' 9 1/16"
B	9' 4"
C	13' 6 9/16"
D	17' 2 15/16"
E	20' 3 5/16"
F	22' 6 3/8"
G	23' 11"
H	24' 4 5/8"


CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 12' 2 5/16"
 BIN RADIUS: 11' 11 1/4"



27' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 9 1/16"
B	9' 4 5/16"
C	13' 8 3/16"
D	17' 7 1/8"
E	20' 11 5/8"
F	23' 8 7/16"
G	25' 8 5/8"
H	26' 11 7/16"
I	27' 4 7/16"


CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 13' 8 3/16"
 BIN RADIUS: 13' 5 1/8"



30' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 9"
B	9' 4 9/16"
C	13' 9 3/8"
D	17' 10 1/8"
E	21' 5 9/16"
F	24' 6 11/16"
G	27' 9/16"
H	28' 10 7/16"
I	29' 11 3/4"
J	30' 4 1/4"


CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 15' 2 1/8"
 BIN RADIUS: 14' 11 1/32"



33' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 8 15/16"
B	9' 4 11/16"
C	13' 10 3/16"
D	18' 5/16"
E	21' 10"
F	25' 2 3/8"
G	28' 9/16"
H	30' 3 15/16"
I	31' 11 7/8"
J	33'
K	33' 4 1/16"


CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 16' 8"
 BIN RADIUS: 16' 4 15/16"



36' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 8 7/8"
B	9' 4 13/16"
C	13' 10 13/16"
D	18' 1 15/16"
E	22' 1 3/8"
F	25' 8 3/16"
G	28' 9 13/16"
H	31' 5 1/2"
I	33' 6 11/16"
J	35' 1"
K	36' 1/8"
L	36' 3 7/8"

CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 18' 1 15/16"
 BIN RADIUS: 17' 10 7/8"




**39' DIAMETER
COMMERCIAL BIN
ANCHOR PLACEMENT**

POINT	DISTANCE
A	4' 8 7/8"
B	9' 4 7/8"
C	13' 11 1/4"
D	18' 3 3/16"
E	22' 3 15/16"
F	26' 13/16"
G	29' 5 1/16"
H	32' 4 3/16"
I	34' 9 11/16"
J	36' 9 1/16"
K	38' 2"
L	39' 1/4"
M	39' 3 11/16"

CONCRETE RADIUS: SEE CHART
ANCHOR RADIUS: 19' 7 7/8"
BIN RADIUS: 19' 4 3/4"

SWB0264
03/26/2012 EAB




**42' DIAMETER
ANCHOR PLACEMENT**

POINT	DISTANCE
A	4' 8 13/16"
B	9' 4 15/16"
C	13' 11 5/8"
D	18' 4 3/16"
E	22' 6"
F	26' 4 7/16"
G	29' 10 7/8"
H	33' 3/4"
I	35' 9 11/16"
J	38' 1 1/4"
K	39' 11"
L	41' 2 3/4"
M	42' 5/16"
N	42' 3 1/2"

CONCRETE RADIUS: See Chart
ANCHOR RADIUS: 21' 1 3/4"
BIN RADIUS: 20' 10 11/16"

SWB0073
060823 EAB




45' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 8 13/16"
B	9' 4 15/16"
C	13' 11 7/8"
D	18' 5"
E	22' 7 5/8"
F	26' 7 5/16"
G	30' 3 1/2"
H	33' 7 3/4"
I	36' 7 1/2"
J	39' 2 1/2"
K	41' 4 5/16"
L	43' 11/16"
M	44' 3 3/8"
N	45' 5/16"
P	45' 3 1/4"

CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 22' 7 5/8"
 BIN RADIUS: 22' 4 9/16"

SWB0285
 03/26/2013 EAB




48' DIAMETER ANCHOR PLACEMENT

POINT	DISTANCE
A	4' 8 3/4"
B	9' 5"
C	14' 1 1/16"
D	18' 5 5/8"
E	22' 8 15/16"
F	26' 9 11/16"
G	30' 7 3/8"
H	34' 1 7/16"
I	37' 3 5/8"
J	40' 1 1/2"
K	42' 6 11/16"
L	44' 7"
M	46' 2 1/8"
N	47' 3 15/16"
P	48' 1/4"
Q	48' 3 1/16"

CONCRETE RADIUS: See Chart
 ANCHOR RADIUS: 24' 1 1/2"
 BIN RADIUS: 23' 10 1/2"

SWB0074
 060823 EAB



Farm Bin Anchor Bolt Guidelines


- Based on ASCE 7-16 Code, 105 mph wind zone -

A qualified geotechnical engineer should review all foundation specifications, including anchor bolt layout, to ensure foundation design is compatible with maximum load-bearing capacity of soil and with any other environmental factors at bin location.

Tables on next page are provided as general guidance for minimum anchor bolt requirements (diameter and depth in concrete). Pull-out force depends on diameter of anchor. Mechanical drill and drive anchors require ultimate pull-out strength of 7,500 lbs. for 5/8" and 10,000 lbs. for 3/4" anchor bolts. Be certain to follow anchor bolt manufacturer's detailed installation instructions to prevent any uplift. Also, it is important these guidelines be followed to ensure proper anchoring:

- Concrete pad must be allowed to cure for a minimum of 28 days prior to anchoring of bin.
- Unless otherwise noted by anchor bolt manufacturer, holes must be cleaned by using a wire brush and air to blow out dust. Cleaning hole will minimize slippage after wedge/epoxy anchor is set.
- Nuts on anchors must be tightened to manufacturer's specifications to withstand uplift.

Drawing below shows types of anchors used. At left are two different types of cast-in-place anchor: an "L" style and a "W & N" (washer and nut) style. At right are two different post-installed anchors: a mechanical drill and drive style and a drill and epoxy style.



Farm Bin Anchors

Bin Dia.	Bin Height (Rings)	Type of Anchor*			Depth In Concrete	Washer Qty. Per Anchor (in bin box)		
		Cast In Place	Drill & Epoxy	Mechanical Drill & Drive		2-3/4" x 3-1/2" BS52082	5/8" Flat J1127	3/4" Flat J1130
15'	3-7	5/8" L	5/8"	5/8"	6-1/2"	1	1	-
	8-10	3/4" L	3/4"	**	8"	1	-	1
18'	3-6	5/8" L	5/8"	5/8"	6-1/2"	1	1	-
	7-10	3/4" L	3/4"	**	8"	1	-	1
21'	3-6	5/8" L	5/8"	5/8"	6-1/2"	1	1	-
	7-10	3/4" L	3/4"	**	8"	1	-	1
24'	3-6	5/8" L	5/8"	5/8"	6-1/2"	1	1	-
	7-10			**	8"	1	-	1
27'	3-6	5/8" L	5/8"	5/8"	6-1/2"	1	1	-
	7-10			**	8"	1	-	1
30'	3-6	3/4" L	3/4"	3/4"	8"	1	-	-
	7-10			**				
33'	3-6	3/4" L	3/4"	3/4"	8"	1	-	-
	7-10			**				
36'	3-9	3/4" L	3/4"	3/4"	8"	1	-	-
	10			**				
42'	3-9	3/4" L	3/4"	3/4"	8"	1	-	-
	10			**				
48'	3-10	3/4" L	3/4"	3/4"	8"	1	-	-

*See previous page for anchor types ("L" refers to shape of anchor).

Mechanical drill & drive anchors **NOT RECOMMENDED by Sukup Manufacturing Co.

Farm Stiffened Bin Anchors

Bin Dia.	Bin Height (Rings)	Type of Anchor*			Depth In Concrete	Washer Qty. Per Anchor (in bin box)	
		Cast In Place	Drill & Epoxy	Mechanical Drill & Drive		2-3/4" x 3-1/2" BS52082	5/8" Flat J1127
15'	5-7	5/8" L	5/8"	5/8"	6-1/2"	1	1
	8-9	3/4" W & N	3/4"	**	8"	2	-
18'	5-7	5/8" L	5/8"	5/8"	6-1/2"	1	1
	8-9	3/4" W & N	3/4"	**	8"	2	-
21'	5-8	5/8" L	5/8"	5/8"	6-1/2"	1	1
	9-10	3/4" L	3/4"	**	8"	2	-
24'	5-8	5/8" L	5/8"	5/8"	6-1/2"	1	1
	9-10	3/4" L	3/4"	**	8"	2	-
27'	5-8	5/8" L	5/8"	5/8"	6-1/2"	1	1
	9-10	3/4" L	3/4"	**	8"	2	-
30'	5-8	5/8" L	5/8"	5/8"	6-1/2"	1	1
	9-11	3/4" L	3/4"	**	8"	2	-
33'	5-8	3/4" L	3/4"	3/4"	8"	1	-
	9-12	3/4" L	3/4"	**	8"	2	-
36'	5-8	3/4" L	3/4"	3/4"	8"	1	-
	9-12	3/4" L	3/4"	**	8"	2	-
42'	5-8	3/4" L	3/4"	3/4"	8"	1	-
	9-12	3/4" L	3/4"	**	8"	2	-
48'	5-9	3/4" L	3/4"	3/4"	8"	1	-
	10-12	3/4" L	3/4"	**	8"	2	-

*See previous page for anchor types ("L" refers to shape of anchor; "W & N" refers to washer and nut).

Mechanical drill & drive anchors **NOT RECOMMENDED by Sukup Manufacturing Co.


15' - 48' 5K Roof Assembly

Prior to assembly of roof it will be necessary to assemble first (top) ring of bin sidewall. Refer to sidewall assembly section of this manual for proper instructions. **NOTE:** For best results, unless otherwise specified, leave all bolts loose until roof assembly is complete. When tightening 3/8" bolts, torque to 25-35 ft.-lbs. For ease of construction, assemble apron on a flat surface.

IMPORTANT: At no time should any bolts be substituted for those supplied by Sukup Manufacturing Co.

DISCLAIMER: Roof is non load-bearing. It is not designed to support catwalks or accessories other than vents and roof ladder rungs.


Eave Clip Assembly



Install eave clips on top horizontal bolt holes around sidewall ring. Eave clips are to be installed on **inside** of bin sidewall as shown in Fig. 1. Begin by installing 3/8 x 1" bolts in every hole and tighten with 3/8" flange nuts. Continue installing eave clips, alternating from a rib clip to an intermediate clip, and fastening in place with 3/8" flange nuts. **NOTE:** When installing first clip, make certain of location. If started incorrectly, roof manhole and roof ladder may not line up properly.

Attachment of Continuous Eave Clip (Y Option)

IMPORTANT: Use continuous eave clip on hopper bins.



Attach continuous eave clip to top row of holes on **outside** of each bin sidewall sheet as shown in Fig. 2. Fasten with 3/8 x 1" bin bolts and 3/8" flange nuts. Insert bolts from inside of bin. Rib tabs can be bent back into roof sheet rib after all roof sheets have been assembled to peak ring and eave clip.

Peak Ring Apron Assembly




Fig. 3

Locate peak ring. Apply caulk to underside of flange, one strip above bolt holes and one strip below, around entire circumference. See Fig. 3.

Table 1 shows part numbers and quantities of peak ring apron pieces used for each size of bin, including number of tabs per apron piece.

BIN DIA.	APRON A PART #	APRON A QTY.	APRON A TAB QTY.	APRON B PART #	APRON B QTY.	APRON B TAB QTY.
15'	B5364	3	3	B53641	3	2
18'	B53662	6	3	--	--	--
21'	B53673	7	3	--	--	--
24'	B53682	6	4	--	--	--
27'	B53692	3	5	B53693	3	4
30'	B53702	6	5	--	--	--
33'	B53712	3	6	B53713	3	5
36'	B53722	6	6	--	--	--
39'	B5376	3	6	B53761	3	7
42'	B53732	6	7	--	--	--
48'	B53742	6	8	--	--	--

Table 1

On tab side of apron, apply a strip of caulk between apron edge and bolt seam as shown in Fig. 3. **IMPORTANT:** There are more holes than needed to align apron pieces to peak ring. Fill all necessary holes. Attach first apron piece to underside of peak ring with 5/16 x 1-1/4" bin bolts and 5/16" flange nuts. Working counterclockwise, overlap apron pieces and fasten seams using 5/16 x 1-1/4" bin bolts and 5/16" flange nuts. Tabless side of apron pieces will always overlap tab side. Alternate between aprons of different size, if applicable, as working around peak ring. See Fig. 3. Continue fastening apron pieces and complete assembly of apron to peak ring.

Peak Stiffening Ring Assembly (39', 42', & 48' bins)





Fig. 4

On 39', 42' and 48' diameter bins and all bins with a stirring machine, a peak stiffening ring is used. **NOTE:** If peak stiffening ring is used, hardware must be tightened at apron-to-peak-ring connection before peak stiffening ring can be attached. This will allow flange nut access from inside to ensure a watertight seal. Connect peak stiffening ring to peak ring with (12) 5/16 x 1-1/4" bin bolts and 5/16" flange nuts. See Fig. 4. Ensure slide rod holes line up in peak ring and peak stiffening ring.

On 42' and 48' diameter bins, apron support brackets are used to provide greater strength. Assemble apron support brackets on underside of aprons at every seam using 5/16 x 1-1/4" bin bolts and 5/16" flange nuts. See Fig. 4. Field-drill bolt holes in peak ring as needed for connection of apron support brackets.

Initial Roof Sheet Assembly



Place support jack in center of sidewall ring. See Table 2 for approximate height setting. This height is a starting point. Peak ring may need to be raised or lowered to ensure that holes in roof sheets match up with holes in eave clips. **NOTE:** An **adjustable** center support jack will allow for incremental adjustments, making assembly of roof to eave clips easier. See Fig. 5.

Bin Diameter	Approx. 5K Roof Peak Ring Height
15'	8'
18'	8' 11"
21'	9' 11"
24'	11'
27'	11' 9"
30'	12' 8"
33'	13' 7"
36'	14' 11"
39'	15' 8"
42'	16' 5"
48'	18' 3"

Table 2

NOTE: Measurements must be taken from foundation to top of peak ring.

If possible, fasten peak ring to center support jack using upper horizontal slots. Position holes for peak ring cap slide rods to be opposite of intended location of roof ladder. This will permit peak ring cap to slide away from roof ladder when cap is opened for filling bin.

Begin roof assembly by installing three (3) or four (4) individual roof panels, depending on bin diameter, so they form a triangle or cross, as shown in Fig. 5. Use 5/16 x 1-1/4" bolts and 5/16" flange nuts.

Roof Sheet Assembly




Fig. 6

Attach top of roof sheet to apron using two (2) 5/16 x 1-1/4" bolts and 5/16" flange nuts. See Fig. 6. Leave bolts out of right-hand rib at top, as shown. This will allow assembly in **counterclockwise** direction. Leaving this rib unattached will allow next roof panel to slide into place.





Fig. 7

Fasten bottom of roof panel to eave clips (shown in Fig. 7) or to continuous eave clip (See Fig. 2) using 5/16 x 1-1/4" bolts and 5/16" flange nuts. Leave out bolt closest to left-hand rib. Rib will be lifted later for assembly of last roof panel.

Slide next roof panel into place, overlapping ribs as shown in Fig. 8. Lay panel flat when sliding it up roof to prevent gouging of roof panel already in place. Place two (2) or three (3) panels in each section, then move to opposite side and do same. Fasten panels to apron and continuous eave clip using 5/16 x 1-1/4" bolts and 5/16" flange nuts.

Connect roof sheets to one another with 5/16 x 1-1/4" bolts in all pre-drilled holes in ribs. Finger-tighten from below using 5/16" flange nuts. Lift starter sheet to install last roof sheet. **NOTE:** Leave out bolts at locations of roof ladder rungs and roof ring brackets.

Add bent roof ring brackets at appropriate locations with openings toward peak ring. See Table 5 for locations of bent roof ring brackets. **NOTE:** 39', 42' and 48' diameter bins have two (2) roof rings. An exception is 48' Sukup Europe bin, which has three (3) roof rings. See Table 5.1.





Roof Ladder Rungs and Bent Roof Ring Brackets

During roof sheet attachment, attach roof ladder rungs and roof ring brackets to roof sheet ribs using 5/16 x 1-1/4" bolts, steel-backed washers and 5/16" flange nuts (under roof sheet ribs). See Fig. 9. Ensure rounded edge of each rung faces top of bin and that roof ladder will be adjacent to roof manhole. Washers must be tight against roof sheet ribs to ensure watertight seal. Omit ladder rungs where roof ring(s) will interfere.

If required, attach roof ladder supports while attaching rungs. See next page.

Attach peak walk-around rungs over every other panel as shown in Fig. 9. Use same process as above.

Roof ring bracket, roof ring, and U-bolt assemblies are shown in Figs. 13 and 14.



Roof Ladder Support Assembly




Fig. 10

When assembling roof ladder rungs on 36' diameter or larger bin, simultaneously install roof ladder supports to underside of roof ribs. Splice roof ladder supports as shown in Fig. 10 using 5/16 x 1" bolts and 5/16" flange nuts.

Attach roof ladder supports under roof ribs starting at second hole from bottom of rib. Roof ladder supports and roof ladder rungs are connected using 5/16 x 1-1/4" bolts, steel-backed washers and 5/16" flange nuts. See Table 3 for roof ladder support specifications.

Table 3

Bin Diameter	QTY./Rib	Part #	Roof Ladder Support Length
36'	1	B5791	82.252"
	1	B5792	102.815"
39'	2	B5792	102.815"
42'	1	B5790	61.689"
	2	B5791	82.252"
48'	1	B5790	61.689"
	2	B5792	102.815"


Roof Ladder Support Splice Specifications

Bin Diameter	# of Splices Required
36'	1
39'	1
42', 48'	2

15', 18', 21', 24', 27', 30' and 33' diameter bins do not require roof ladder supports.

1/8" Foam Sealant and Inner Shield

Fig. 11



When all roof panels and bolts are in place, install foam sealant and inner shields on ends of roof panels under roof apron. See Fig. 11. Roll of foam sealant may be longer than needed. Unroll foam sealant around inside of roof panel ends and cut to appropriate length. **TIP:** Once length has been determined, it may be easier to cut foam sealant to same length as flashing. Sealant can then be applied to each piece of flashing.




Fig. 12

As shown in Fig. 12, insert three (3) shield pieces, then tighten bolts on first installed piece. Install fourth piece and tighten next set of bolts. Continue pattern until all inner shields are installed. See Table 4 for quantity of peak ring inner shields. **TIP:** After shield pieces are put into place, run a self-tapping screw through every overlapped location. This will tie pieces together and secure them in place.

Bin Diameter	Shield piece QTY.
15' – 36'	15
42' – 48'	20

Table 4 – Quantity of peak ring inner shield pieces, Part # B53653

IMPORTANT: Tighten all 5/16" flange nuts to 15 to 20 ft.-lbs.

Using a soft-faced mallet, bend down tabs on apron until contact is made with roof panel.

External Roof Ring Attachment

See Table 5 for quantities of roof ring components based on bin diameter. Bent roof ring brackets should have been fastened at locations specified in Table 5 during assembly of roof panels.

Table 5 – Quantities of roof ring components

Bin Dia.	Bent Bracket, Roof Ring Location*	Internal Tube Splices	Expanders	10' Pieces **	U-Bolts	External Splice Tubes
18'	3	1	2	4	18	1
21'	3	2	2	5	21	1
24'	4	2	2	5	24	1
27'	4	2	3	6	27	1
30'	5	2	3	6	30	1
33'	5	3	3	7	33	1
36'	5	3	4	8	36	1
39'	5	4	4	9	39	1
	7	3	3	7	39	1
42'	5	4	5	10	42	1
	10***	2	3	6	42	1
48'****	6	5	5	11	48	1
	11	2	3	6	48	1

* Location determined by counting holes from bottom edge (eave) of roof sheet.

** Roof ring pieces are factory-rolled for intended location.

*** If using tapered roof vent on 42' bin, upper ring must be at 9th hole from eave instead of 10th.

****48' Sukup Europe bins require three roof rings. See Table 5.1 below

48'	4	6	6	13	48	1
	6	5	5	11	48	1
	11	2	3	6	48	1

Pre-assemble expander assemblies (1 x 10" threaded rod, 1" nuts and 1" washers) before installing ring. Run all four (4) 1" nuts to center of each threaded expansion rod. Position washers outside of nuts. Nuts and washers will be run outward later after all sections of ring have been assembled. See Fig. 13.






Fig. 13

Place first expander assembly near roof ladder. Center first ring section on roof ladder sheet. Evenly space remaining expanders around roof ring as ring sections are placed into bent roof ring brackets. Install internal tube splices (B5511) at all other locations except last one, where an external splice tube will be used.

Fig. 14 shows 8" internal tube splice using a 5/16 x 1-1/4" bin bolt as a stopper. Fig. 15 shows 8" external splice tube (B5512) using 5/16 x 2" bolt. Place 5/16" U-bolts on all roof ring mounting brackets. See Figs. 13 and 14. Do not tighten U-bolt flange nuts until later, after roof has been crowned.



External splice tube will be installed after all other splices and expanders are in place and ring sections are trimmed. If final section of roof ring will be less than 24" long, split the difference with previously assembled roof ring section and create two sections of equal length. See Fig. 15. Ensure there is a 3/8" gap between ring sections for bolt that will be inserted. It may be necessary to deburr cut edges.



Slide external splice tube (B5512) over one end of roof ring. Align ring sections and position splice over both. Insert 5/16 x 2" bolt into splice tube and lock in place with 5/16" flange nut.

Adjust expander assembly nuts until a slight crown appears in middle of roof sheets. Tighten second set of nuts (jam nuts) against expander nuts to help prevent loosening. Tighten 5/16" flange nuts on 5/16" U-bolts at all bent roof ring brackets.

NOTICE: Roof ring will fail if expander assemblies become loose due to high winds or excessive pressures. To guard against failure, be sure to follow procedures on these pages when installing ring.

2-1/2" Internal Roof Ring

Table 6 – Quantities of internal roof ring components

Farm Bin	Bin Dia.	2-1/2" Internal Roof Ring Pkg.	Locating Holes*	Mounting Brackets BC3106	Internal Support Brackets B5790	18' 9" Tube 2-1/2" Dia.	2-1/2" Tube Splice Assy. BC3101**
Option	24'	BC8241	4, 5 & 6	8	8	5 (12')***	5
Option	27'	BC8271	4, 5 & 6	9	9	3 (15')	3
Option	30'	BC8301	5, 6 & 7	10	10	3 (15')	3
Option	33'	BC8331	5, 6 & 7	11	11	4 (18')	4
Option	36'	BC8361	5, 6 & 7	12	12	4 (21')	4
Option	42'	BC8421	5, 6 & 7	14	14	5 (27')	5
Option	48'	BC8481	5, 6 & 7	16	16	6 (33')	6

* Location determined by counting holes from bottom edge (eave) of roof sheet.

** Two (2) formed pieces (BC3101) required at each splice assembly location.

*** 12' wind ring pieces are 9' 4-1/2" long instead of 18' 9" long

Internal roof ring support brackets are to be attached to roof ribs at every third (3rd) roof sheet. It is recommended that brackets and 2-1/2" internal roof rings be installed after outer roof rings are attached, expanded, and U-bolts tightened. These roof ring support brackets can be attached over existing flange nuts if roof is already completely tightened. See Table 6 to determine amount of hardware used.




Fig. 16

NOTE: Fig. 16 shows installation of 2-1/2" internal roof ring. Support bracket is reversible for ease of assembly. Use 2-1/2" mounting brackets to attach internal roof ring to support brackets. Use bottom set of holes with 3/8 x 1-1/4" bolts and 3/8" flange nuts.

After external roof rings are expanded and U-bolts tightened, attach 2-1/2" internal roof ring sections to support brackets as shown in Fig. 17. Tube sections should be attached to one another with tube splices, 3/8 x 1-1/4" bolts and 3/8" nuts. Screw 1/4 x 1" self-drilling screws into each tube section to reduce any slack or gaps that may occur during assembly. Final section of tube needs to be cut off so final section butts up against first section without any gap between them. A minimum of about 64-3/4" should be cut off. This dimension may vary due to expansion of external roof rings.




Fig. 17

SWB0251
6/4/2010BAP

Manhole Cover Assembly (B5380)




Fig. 18 & Table 7

ITEM	PART #	DESCRIPTION	QTY.
1	B5381	Cover	1
2	B5384	Riser assembly	1
3	B5387	Hinge	1
4	J3232	Handle	1
5	B5388	Lid bracket	2
6	J23073	Rubber latch strap	2
7	B23074	Anchor bracket	2
8	J15443	Picker pin, 1/4 x 1-1/2"	2
9	J1419	Cotter pin, 1/16 x 3/4"	2
10	J5666	Clamp, 5/16"	4
11	J0504	Bolt, 1/4 - 20 x 1/2"	10
12	J09923	Flange nut, 1/4"	10
13	J70955	Vinyl edge guard (Not shown)	1

Attach two clamps (Item 10) to hinge (Item 3) that was factory-attached to lid and then attach them to outside of pre-assembled manhole riser (Item 2) using 1/4 – 20 x 1/2" bolts (Item 11) and 1/4" flange nuts (Item 12). Ensure lid will open away from sidewall ladder/platform for ease of access into bin through manhole. Insert bolts from inside of riser as shown. Tighten 1/4" hardware after ensuring lid will open and close with ease. **NOTE:** Notches in top of riser eliminate interference between hinge and riser as lid is closed.

Attach vinyl edge guard (Item 13) to top edge of riser. Cut vinyl edge guard over notches on hinge side of riser to avoid interference with hinge.

Attach rubber latch straps (Item 6) to factory-attached anchor brackets (Item 7) and secure each with a picker pin (Item 8) and cotter pin (Item 9).

Ensure rubber straps secure lid by locking it down on riser.

Peak Ring Cap Assembly

Fig. 19




Table 8 – Peak ring cap components

REF. #	DESCRIPTION	QTY.	PART #
1	Peak ring cover, w/ holes	1	B53612
2	Fill cap rod	2	B5361-01
3*	Fill cap handle	1	B5361-02
4	Flat washer, 3/8"	8	J1117
5	Hex nut, 3/8" - 16	8	J1020
6*	Bolt, 1/4 - 20 x 1/2"	4	J0504
7*	Hex nut, 1/4" - 20	4	J0990
8	Spring-loaded latch	1	J2298
9*	Latch catch	1	J2297

*Items 3, 6, 7 & 9 included in lid handle assy. B5361

Attach fill cap handle to front of peak ring cover with two 1/4 - 20 x 1/2" bolts and 1/4" lock nuts. See Fig. 19. **NOTE:** Latch catch is pre-assembled to handle. Make certain open end is facing upward.

Slide long ends of fill cap rods through holes in peak ring, then thread a 3/8" hex nut onto each end of each fill cap rod and slide a 3/8" flat washer over each end. Slide long ends of rods through holes in back of cap and short ends through top of cap as shown in Fig. 19. Slide a second 3/8" flat washer onto each end of each rod, followed by a second 3/8" hex nut. Adjust so hex nuts on top of cap are flush with ends of slide rods, then tighten inside nuts. Slide lid closed and center on peak ring.

Hang spring-loaded latch from latch catch. Extend spring-loaded latch until it comes into contact with apron. Mark and field-drill latch location. Attach spring-loaded latch to apron with 1/4 - 20 x 1/2" bolts and 1/4" hex nuts.

Attach peak ring cap bracket to roof rib as shown in Fig. 20, making sure to use hole specific to bin diameter.

NOTE: If spiral stairs will be installed, use a grinder or tin snips to trim or round off corners of roof panels to prevent accidental snagging.




Fig. 20

Poly Roof Vent Assembly

Follow instructions on this and next page to install Poly Roof Vent. If using optional snow guard, attach as shown in Fig. 23 before screen is attached to vent. See Fig. 24 and related instructions for attaching braces to vents on bins in ASCE 7-16 Code, 136 mph or higher wind zone.




Fig. 21

Insert 5/16 x 1-1/4" bolts into pivoting screen holes from outside in as shown above. Tighten to poly vent with 5/16" flange nuts. Work the pivoting screen bolt hole loops over the 5/16 x 1-1/4" bolts with loops bent up as shown in Detail A. Screen should be attached so it will be at a slight angle when vent is attached to roof. Screen should not be vertical. Fasten 5/16" lock nuts to ends of 5/16" bolts as shown above to ensure screen stays in place and can pivot freely on bolts. Attach vent spreader bar as shown above using 5/16" bolt and flange nut. Ensure loops are bent upward.

Tabs of front bracket should be nested inside of poly vent. Apply butyl caulk to front edges of roof vent to ensure a watertight seal when front bracket is fastened.

Attach front bracket to poly roof vent using 5/16 x 1-1/4" bolts and 5/16" flange nuts. Tighten all hardware.




Fig. 22

Apply two strips of butyl caulk around cutout, one on each side of mounting holes, as shown in Fig. 22. Additional butyl caulk is provided to apply a double stack on top side of roof vent cutout. Apply butyl caulk close to mounting holes, leaving a 1" gap around outside strip.

Attach roof vent and two inside support brackets (D39366) to roof sheet using 5/16 x 1-1/4" bolts, 5/16" fender washers and 5/16" flange nuts as shown in Fig. 22. Use 5/16" fender washers on top side of poly flange. **NOTE:** To prevent damage to poly roof vent flanges, secure vent to roof by tightening nuts on underside of roof sheet instead of tightening bolts on top side. To prevent puckering of vent flanges, do not over-tighten nuts.

Check sealant along top side of roof vent base for any gaps or pockets. Apply a bead of tube caulk (not provided) along top side of base to ensure a watertight seal.

IMPORTANT: Check caulk along top side of base yearly and re-apply as needed to prevent leakage.

Attaching Optional Snow Guard & Vent Braces

Attach optional snow guard to vent screen as shown in Fig. 23 using 5/16" hardware.




Fig. 23

Braces for Vents in 136 mph or Higher Wind Zones

Add braces to poly roof vents to provide greater stability on bins in ASCE 7-16 Code, 136 mph or higher wind zone.

Adjust braces so that holes on flat ends will attach to sides of roof vent and to top of roof sheet ribs as shown in Fig. 24. Position braces so they are spaced out as much as possible.

After ensuring vent brace alignment, drill holes in sides of roof vent and top of roof ribs.

Use 5/16" hardware to attach D3936P7 braces to all four (4) corners of roof vent.




Fig. 24

SWB0318
08/10/2015 JLT

Tapered Poly Roof Vent Assembly




Fig. 25

Position pre-assembled vent close to peak of bin, leaving enough room to attach vent to flat area of roof sheet and allow for drainage around vent. Remove lid and screen by unscrewing six (6) 5/16 x 1-1/4" bolts from nut inserts in body of vent. Use inside of vent wall as a guide for marking roof sheet cutout opening. Draw lines for cutout 1" inside of vent sides. Set vent body aside. Cut vent hole in roof sheet, bending edges upward to create a flange that will help prevent water from leaking in. Position vent body over cutout. Use pre-punched holes in vent flanges as templates for drilling attachment holes in roof sheet. Set vent body aside.

Apply two strips of butyl caulk around cutout, with one strip on each side of mounting holes.

Attach body of vent to roof using 5/16 x 1-1/4" bolts, 5/16" fender washers and 5/16" flange nuts.

NOTE: To prevent damage to poly roof vent flanges, secure vent to roof by tightening nuts on underside of roof sheet instead of tightening bolts on outside.

Check sealant along top end and sides of vent body for any gaps or pockets. Apply a bead of tube caulk (not provided) along top end and sides of body to ensure a watertight seal.

Re-attach lid and screen to body of vent using hardware previously removed.

IMPORTANT: Check caulk around vent yearly and re-apply as needed to prevent leakage.

Temperature Cable Support Packages

There are two types of support package – roof rib support package and center support package. Depending on bin diameter, a Sukup Farm-Duty bin requires up to five (5) roof rib support packages and one (1) center support package. See Table 9 and Figs. 28-31 for cable locations.

IMPORTANT: Note locations of internal roof rings. If temp cable hanger(s) would interfere, mount as close as possible to hanger location(s) specified in drawing.

Roof Rib Support Package:

Consists of two (2) roof rib supports, one (1) hanger bar, two (2) support brackets, one (1) shackle, eight (8) 5/16" bolts and eight (8) flange nuts.




Fig. 26 – Installing temp cable support package B41001 for 24' to 48' dia. bins

Installation requires field-drilling each roof rib support (B5790) for attachment of temp cable support bracket (B41021). Attach roof rib supports to roof ribs as shown in Fig. 26 using existing holes. Center of roof rib support should be located close to temperature cable radius shown in Table 9 and applicable drawing (Figs. 28-31). Drill three (3) holes into side of each roof rib support, using B41021 bracket as drill guide. Attach each B41021 bracket to roof rib support using three (3) 5/16 x 1-1/4" bolts (B5952) and 5/16" flange nuts.

Place hanger bar (B4101) in slots of B41021 brackets and put a bolt and nut on each end of bar. There are three (3) holes on each end of bar. Place bolt in closest hole to outside of each bracket, making sure bar is centered between brackets. A shackle (J7900) is provided to hang temperature cable from bar. Attach shackle to bar at center hole.

Center Support Package:

Consists of one (1) hanger bar, two (2) support brackets, one (1) shackle, six (6) 5/16" bolts and six (6) flange nuts. See Fig. 27.





Fig. 27




Hook left and right hanger bar supports to peak ring directly across from one another and use as templates to drill holes for attachment bolts (two for each support). Bolt both supports to peak ring, making sure bolt heads are outside and nuts are inside of ring. Place hanger bar between brackets. See Fig. 27. There are three (3) holes on each end of bar. Place bolt in closest hole to outside of each bracket, making sure bar is centered between brackets. Make sure bar goes full diameter of peak ring. A shackle (J7900) is provided to hang temperature cable from bar. Attach shackle to bar at center hole.

Bin Diameter (ft.)	Number of Sidewall Rings	Center Support Package	Roof Rib Support Package	Location
15	4-10	1	--	Center
18	4-10	1	--	Center
21	4-10	1	--	Center
24	4-10	--	3	@ 4' Radius
27	4-10	--	3	@ 5' Radius
30	4-10	--	3	@ 6' Radius
33	4-10	--	3	@ 8' Radius
36	4-10	--	3	@ 8' Radius
39	4-10	1	3	1 @ Ctr., 3 @ 10' R
39	11-24			NA
42	4-10	1	4	1 @ Ctr., 4 @ 11' R
42	11-24			NA
48	4-10	1	5	1 @ Ctr., 5 @ 16' R
48	11-24			NA

Table 9 – Temperature cable support placement on Sukup 5K roof

- Do not attach more temperature cable support packages than recommended.
- Follow operating instructions provided by temperature cable provider.


36' TEMP CABLE LAYOUT -- 4 CABLES



SWBC0354
12/08/2023 AAH

1 CABLE ON CENTER
3 CABLES ON 8 FT. RADIUS **Fig. 28**


39' TEMP CABLE LAYOUT -- 5 CABLES



SWBC0355
12/20/2023 AAH

1 CABLE ON CENTER
4 CABLES ON 10 FT. RADIUS **Fig. 29**


42' TEMP CABLE LAYOUT -- 5 CABLES



SWBC0353
12/08/2023 AAH

1 CABLE ON CENTER
4 CABLES ON 11 FT. RADIUS **Fig. 30**

48' TEMP CABLE LAYOUT -- 6 CABLES



SWBC0352
12/07/2023 AAH

1 CABLE ON CENTER
5 CABLES ON 16 FT. RADIUS **Fig. 31**

Knot-Passing Pulley & Restraint Anchor Installation

For added safety, a knot-passing pulley is mounted to peak ring of roof rated for 5,000 to 8,000 pounds. Pulley is intended to be used with a lifeline and safety harness (neither supplied by Sukup Manufacturing Co.). A feeder line should pass through knot-passing pulley and through restraint anchor at eave of bin near manhole. Feeder line is used to pull lifeline through knot-passing pulley for safety harness attachment. Do not attach safety harness to feeder line. Use safety equipment according to manufacturers' instructions. Refer to Sukup Grain Bin Operation Manual Safety Section and www.osha.gov for additional safety information.

NOTE: For ease of installation, it is best to install knot-passing pulley during assembly of roof and restraint anchor during assembly of first (top) ring of bin.




Fig. 32 – Knot-passing pulley, restraint anchor & J-hook installation

Each kit contains knot-passing pulley, bracket, restraint anchor, rope for feeder line, J-hook, decals and hardware needed for mounting pulley, restraint anchor and J-hook.

Table 10

KIT #	BIN DIAMETER, ROOF RATING	ROPE (FT.)
B0533	12'-33', 5K	36
B0548	36'-48', 5K & 8K	54

IMPORTANT: Attach knot-passing pulley to peak ring so pulley will align with restraint anchor on sidewall near manhole. Ensure that any temperature cables, grain spreader and/or stirring machine in bin will not interfere with feeder line.

NOTE: Disregard J-hook installation instructions if bin does not have a stirring machine.

Knot-passing Pulley Installation: Attach B0510 pulley to peak ring as shown in Fig. 33. If there is no peak stiffening ring, mount B0516 bracket as shown at left in Fig. 33. If there is a peak stiffening ring, mount B0516 bracket as shown at right in Fig. 33. If there is a grain spreader, mount B0516 bracket as shown Image 1. In all cases, bracket attaches with two 5/16" x 1-1/4" bolts and two 5/16" nuts. Attach pulley to bracket using J7901 shackle and pin as shown in Fig. 33.






Image 1 – Pulley bracket between stiffening ring & spreader bracket

Restraint Anchor Installation: Install J08621 restraint anchor eyebolt 2" below horizontal line of eave clip bolt holes on inside wall of bin. See Fig. 34. Drill a 1/2" hole below manhole roof sheet rib. Insert J08621 eyebolt as shown, making sure ring is perpendicular to ground, and secure with 1/2" washer and 1/2" flange nut.



Loop feeder line through pulley and restraint anchor, trim as needed and tie ends together so there is minimal sag. See Fig. 32.


IMPORTANT: If bin has a stirring machine, attach J0851 J-hook to top of roof rib to hold feeder line. See Fig. 32. Use hook in bin without a stirring machine to keep feeder line from hanging in grain.

Place decal L0907 inside of bin just under eyebolt. See Fig. 34. Place decal L09073 below manhole outside of bin. **NOTE:** Factory-applied safety decals on manhole sheet also shown.

Farm Stiffened Sidewall Construction

Before starting assembly of grain bin, confirm locations of components. See Foundation Section for typical accessory layout diagram. Locations for door, unload system and fan or fan/heater transition should have been determined before foundation was poured.

NOTE: On a bin with an even number of rings (4, 6, 8, etc.), door will be straight below a vertical seam in first (top) ring. On a bin with an odd number of rings (5, 7, 9, etc.), door will be straight below center of sidewall sheet in first (top) ring. See Fig. 1.



IMPORTANT: If bin door and unload system will be in same sidewall sheet, ensure that sheet is reinforced around cutout for unload system. See Figs. 13 and 14 for cutout reinforcement instructions.

IMPORTANT: Sukup grain bins require snug fit connections. A snug fit is when steel sheets are fully drawn together, allowing for a thin layer of caulk and compressing rubber washers to seal bolt holes. Snug fit is usually attained with a few impacts of an impact wrench. **NOTE:** All 3/8" bolts use flange nuts. Torque to 25-35 ft.-lbs.

IMPORTANT: At no time should any bolts be substituted for those supplied by Sukup Manufacturing Co.

Locate first (top) set of sidewall sheets. Typically these will be lightest gauge of panels. **NOTE:** Larger gauge number means thinner material (For example, 20ga is thinner than 12ga). Refer to color chart that comes with sidewall sheet bundles for exact gauge layout. Use sidewall gauge table at right to identify sidewall sheets by color (painted at corner of sheet). For ease in construction, keep painted edges of panels at same corner for entire ring of bin.

SIDEWALL GAUGE	COLOR	STIFFENER GAUGE
20	RED	
18	GRAY	18
17	BLUE	17
15	WHITE	
14	PINK	14
13	YELLOW	6
12	BLACK	12
11	PURPLE	
10	GREEN	10
9	BROWN	
8	ORANGE	8

ATTENTION: Bin logo panel goes in first (top) ring. Determine suitable location and incorporate into sidewall ring.

IMPORTANT: All sidewall panels are reversible; there is no specific top or bottom. Two exceptions are the first (top) panel if it has been pre-punched for Fastir Stirring Machine track, and last (bottom) panel. Bottom panel may be pre-punched for plenum flashing. Ensure correct location of track and/or plenum flashing holes. For stirring machine track, extra row of bolt holes will be nearest to top edge of panel. See table below for correct location of plenum flashing holes.

HOLE	BOLT-ON BASE ANGLE		
	FLASHING HOLE FROM CONCRETE	SUPPORT	FLASHING
Standard	15"	12-1/2" 13-1/4"	High-back Standard
"F" Option	17"	15-7/8"	Standard
"G" Option	19"	15-7/8" 17"	High-back

Place sidewall panels around perimeter of foundation. Proceed clockwise. After placing first sidewall panel, place next sidewall panel so it overlaps inside of previous sidewall panel. See Fig. 2.

Working clockwise from inside of bin, wipe off vertical panel edges and apply caulk as shown in Fig. 3. Drawing also shows where caulk will be placed later when attaching panels for second ring.

NOTE: Fig. 3 shows assembly proceeding clockwise from inside of bin. If working counterclockwise, ensure proper placement of caulk.




Fig. 2




Fig. 3

Bolt panels together at vertical seam using 3/8 x 1" bolts. Leave very top and bottom seam bolts out, using tapered punches to ensure alignment. Install bolts with head and seal washer on outside and nut on inside. **IMPORTANT:** Do not tighten bolts until ring is completely assembled. Attach 42-7/8" tapered top stiffeners and eave clips. See Fig. 6 and roof section of manual.

NOTICE: To prevent washer damage and moisture leakage, hold **BOLT** stationary while tightening. Spin **NUT** only! See Fig. 4.




Fig. 4

Jack Bolt Usage

Quantity of 3/8 x 2" jack bolts supplied depends on diameter and height of bin. Standard usage is four bolts per jack and one jack per two sidewall sheets. **NOTE:** Generally, more jacks will be used as more rings are added.

Jack bolts are supplied without reducing quantity of standard 3/8 x 1" bolts.

Attach lift brackets for jacks as recommended by jack manufacturer's specifications.


After first (top) ring is complete, assemble roof as outlined in 15' - 48' 5K Roof Assembly section.

When roof assembly is complete, tighten all roof and sidewall bolts. See Ladders, Safety Cages and Platforms section for directions on attaching brackets for inside and outside ladders and/or safety cages and platforms. Install eave safety rails if so equipped. Tighten sidewall bolts after each ring is assembled.

Prepare next ring of panels by wiping clean and applying caulk as shown in Fig. 3. Ensure caulk for horizontal seams is between bottom bolt holes and edge of panel, and that caulk for vertical seams is at edge of panel as shown in Fig. 3.

Using appropriately rated erection jacks, raise bin until bottom of first (top) ring is slightly higher than top of next sidewall sheet.

⚠ WARNING: Never exceed jack manufacturer's stated capacities. Doing so could result in collapse causing death or serious injury.



Attach a second-ring sidewall panel to inside of upper panels as shown in Fig. 5, inserting bolts in all but first and last holes in horizontal seam.

NOTE: Bolts that connect sidewall sheets must be inserted correctly to ensure precise erection of bin. Use tapered punches to properly align bolt holes. Do not leave top and bottom bolt holes of vertical seams for last. Each sidewall sheet – and entire bin -- will fit together better if bolts are inserted in proper sequence. See Fig. 5 Details A and B. Drilling or reaming out bolt holes when sheets are not properly aligned is not recommended unless otherwise specified.


Continue installing second-ring panels until ring is complete. Bolts may be tightened at this time.

IMPORTANT: After each ring has been added and bin jacks are lowered, jack bolts should be removed and replaced with bin bolts of appropriate length.

For assembly instructions for 44" and 66" sidewall doors, see Farm Duty Doors Section.

All Sukup Farm-Stiffened Bins require two (2) stiffeners per sidewall panel. All stiffeners are to be installed on exterior of bin. **NOTE:** Stiffeners will change in gauge (thickness) depending upon location. Be sure to consult Stiffened Bin Sidewall and Stiffener Gauge and Color Code Chart to ensure proper location of stiffener sections.

Start with proper gauge stiffener's top hole aligned with top hole of sidewall sheet. See Fig. 6. Proper vertical alignment of stiffener is important. Take note of where slotted bolt hole in stiffener and sidewall bolt holes in each horizontal seam intersect. Proper vertical alignment of stiffener requires slotted hole to be centered over sidewall horizontal seam bolt hole. See Fig. 6.



All Sukup Farm-Stiffened Bins start with tapered-top stiffener 42-7/8" long. On bins with odd number of rings, continue downward with 88" stiffeners. On bins with even number of rings, continue downward with a 44" stiffener and then with 88" stiffeners. **NOTE:** Stiffener must be positioned correctly. Use tapered punch to ensure proper alignment. Do not allow stiffener to sag or it will result in assembly difficulties.

Fasten stiffener to sidewall using 3/8 x 1" bolts and 3/8" flange nuts. To prevent moisture from entering bin through stiffeners, insert bolts from inside of bin.

Leave two bottom bolts out of stiffener. Likewise, leave out top two bolts on next stiffener. Holes will be used after attachment of splice plates. Continue attaching stiffeners until first tier of stiffeners is complete.




Fig. 7

Continue installing sidewall panels until enough rings are in place for installation of next tier of stiffeners. After installing stiffeners, install splices as shown in Figs. 7 and 8. **NOTE:** Stiffener splices will straddle horizontal sidewall seams. When attaching stiffeners, ensure that gap between upper and lower stiffener is no more than 1/16".




Fig. 8

Attach stiffener splice using 3/8 x 1" bolts and 3/8" flange nuts. **NOTE:** When next stiffener down increases in gauge thickness, stiffener splice plate must also increase in thickness. Always use same gauge splice plate as heaviest stiffener being spliced. Place eight (8) bolts in splice flanges and four (4) bolts through stiffener, neoprene washer and bin sidewall. See Fig. 8.

Continue assembly of bin, including stiffeners, in proper sequence as outlined in Stiffened Bin Sidewall and Stiffener Gauge and Color Code Chart.

NOTE: Use 3/8 x 1" bolts on horizontal seams where 13ga and 12ga panels overlap, and on sidewall panels connected to door frame. This will include short sheets on either side of 44" and 66" doors, as well as 66" door cutout sheet. See Fig. 9.

For bin door assembly and installation, refer to Door Assembly Section.

NOTE: If erecting a hopper bin that doesn't have a door, disregard Fig. 9 and door references in preceding two paragraphs. Refer to hopper section of Hopper Bin manual for instructions on how to attach hopper bottom to bin.




Fig. 9

SWB0113
02162012 MKB

With bottom ring completely assembled, position bolt-on base angle sections. See table to confirm components and quantity needed. **NOTE:** Ensure base angle pieces overlap by one bolt hole. Apply caulk underneath bolt holes as shown in Fig. 10. Bolt base angle to inside of sidewall panel. Use 3/8 x 1" bolts and 3/8" flange nuts.

BIN DIA.	PART #	DESCRIPTION	QTY.
15'	B5721L	Base angle, 15' Dia.	5
18'	B5723L	Base angle, 18' Dia.	6
21'	B5725L	Base angle, 21' Dia.	7
24'	B5724L	Base angle, 24' Dia.	8
27'	B5728L	Base angle, 27' Dia.	9
30'	B5726L	Base angle, 30' Dia.	10
33'	B5731L	Base angle, 33' Dia.	11
36'	B5729L	Base angle, 36' Dia.	12
39'	B5740L	Base angle, 39' Dia.	13
42'	B5727L	Base angle, 42' Dia.	14
48'	B5730L	Base angle, 48' Dia.	16

If foundation sealant is used, apply to bottom of base angle as shown in Fig. 11 before lowering bin onto concrete or hopper bottom. Do not leave gaps between lengths of sealant. One of two types of sealant will be used, depending on diameter of bin. For bins 15' to 33' dia., use 3/8" x 3/4" sealant (J23313). For bins 36' dia. or larger, use 1/2" x 1-1/2" sealant (J23312).

NOTE: All weight should be taken off of bin jacks before base angle bolts are tightened.




Fig. 10

SWB0317
01/07/2019 CLW





Fig. 11

SWB0331
07/26/2018 R.J.H

NOTE: SEE CHART IN ANCHOR BOLT SECTION OF THIS MANUAL FOR SPECIFIC WASHER QUANTITIES



Attach bottom stiffener to sidewall using 3/8" bin bolts. Assemble bolt-on base and bolt-on base support to bottom stiffener with bin bolt and flange nut. Each stiffener will include two shims. One shim is required for thickness of bolt-on base angle. An extra shim is supplied for allowances of uneven concrete surface. See Fig. 12. Attach final stiffener splice and tighten bolts.

Ensure stiffener anchor plates clear foundation anchor bolts and that stiffener anchor pads rest on foundation. One shim per stiffener is required. Shim as necessary any stiffeners not in contact with concrete. Always fill gaps, but never force shims into place.

NOTICE: Failure to ensure proper shimming may result in damage to bin structure.

Ensure circularity of bin and check seal. If foam base sealer is not used, seal inside of bin to concrete foundation using a sealing compound.

Assemble rectangular washer(s) and/or appropriate round washer and nut to anchor bolts. See Farm Stiffened Bin Anchors table elsewhere in this manual for correct number of rectangular washers needed. Make sure rectangular washers are installed with long side toward stiffener, as shown in Fig. 12. Tighten as required by anchor bolt manufacturer's specifications.

Reinforcing Sidewall Cutouts

See Assembly Instructions document L18765 for using Sukup kits to support bin wall around a conveyor. Otherwise, see general instructions below and applicable unload system manual.

Bin sidewall should be reinforced around any cutout wider than 13" (e.g., conveyors). Use 22" anchor brackets or similar supports for cutouts up to 30" wide. See Fig. 13. Attach a base plate (B5701) to each 22" anchor bracket using two (2) 3/8 x 1" bolts and two (2) 3/8" flange nuts. Attach 22" anchor brackets to sidewall using 3/8" bolts.




Fig. 13 – 20" cutout reinforced by 22" anchor brackets (B5700) and base plates (B5701)

For a cutout larger than 30" wide, field-weld C-shaped channel pieces together and attach to sidewall as shown in Fig. 14 using 3/8" bolts.




Fig. 14 – 30" cutout reinforced by C-channel

Stiffener Support at Transition Insert

When a stiffener is located above a transition insert, an anchor (threaded rod) must be welded to transition insert so load from stiffener or bracket can be transferred to bin pad.

If stiffener does not rest on top of a vertical member of transition insert, additional support is needed (minimum of 3" square or round tubing) directly under stiffener column. See Fig. 15. This additional support needs to be welded in place.

NOTE: Ensure each piece of transition insert rebar is tied by wire to stemwall hoop rebar.




Fig. 15 – Supporting stiffener at transition insert

Wind Ring Assembly




Fig. 1

Consult color/gauge chart located either in manual or with sidewall sheets for number of wind rings necessary for bin. Standard wind ring locations are indicated on chart by an "@" symbol. Additional wind rings needed on bin with a sidedraw are indicated by a "+" symbol.

Top stiffeners, 39" & 83", have only one set of holes for wind ring brackets, located two-thirds from top of top ring. The 88" stiffeners are punched with two sets of holes so that wind ring brackets can be attached in middle of sidewall ring. Use bottom holes on bins with odd number of rings. Use top holes on bins with even number of sidewall rings. See Fig. 1.

Unless otherwise stated on color chart, wind rings are located in top ring, third ring, fifth ring and so on (every other ring starting at top). These wind ring locations meet ASAE Standard S412.1 which leaves at least 1-1/2" below the rung and 4-1/2" above the rung where an obstruction (wind ring) is located.




Fig. 2

Loosely attach two wind ring brackets (BC3106) to each stiffener as shown in Fig. 2 using 3/8 x 1-1/4" bolts (B5972) and 3/8" flange nuts (B5962). Insert wind ring sections through brackets.

Butt wind ring sections against each other as shown in Fig. 2. Position splice clamps (BC3101) over ends of wind ring sections. Attach clamps with 3/8 x 1" bolts (B5932) and 3/8" flange nuts (B5962), leaving bolts loose to finger tight. **IMPORTANT:** Splices must be located between stiffeners. Staggering of splices is recommended.

Total length of wind ring sections will be too long for circumference of bin. Last section will need to be cut to butt against first section assembled. Final wind ring section should span at least two sidewall stiffeners.

NOTE: Some wind ring assemblies require that a trimmed piece from a previously assembled ring be used. All leftover sections that are longer than 9' should be saved for possible future use.

Once all wind ring sections have been fastened to stiffeners and spliced, tighten hardware.

Further secure each splice to wind ring using 1/4 x 1" self-drilling screw (J0498) as shown in Fig. 2.

Farm Duty Doors Section

44" & 66" Sidewall Door Installation (D, W, & W1)

NOTE: Use 3/8 x 1" bin bolts for installation of door frames. See Fig. 9 as needed for reference.

Remove inner door panels from frame.

Determine top of frame from bottom. Bottom of frame has sloped sill to direct rain away.

Apply double row of rope caulk to frame flanges. Top flange will receive caulk on outside of flange. Side and bottom flanges will receive caulk on inside, or backside, of flange. See Fig. 1.




Fig. 1

Place door frame into door opening. Top flange of frame will mount inside of sidewall. Side and bottom flanges will mount outside of sidewall panels. Insert 3/8 x 1" bin bolts from outside of bin, leaving nuts loose. Leave bolts out of door hinge support locations. See next page.


NOTE: Second sidewall ring from bottom will have short panels, one on each side of door. 44" door will overlap bottom ring. 66" door overlaps cutout in bottom ring. **NOTE:** See Fig. 7 if installing 44" door on 36' to 48' dia. bin.

Place door panels back into door frame. Make sure they close completely over pegs. Lock hammer-head latches. See Fig. 2. (View is from outside of bin.)

Tighten door frame bolts in sequence shown in Fig. 2. Complete by working around door frame until all bolts are tightened. No particular sequence is required for rest of bolts.

BOLT TIGHTENING SEQUENCE
DOOR PANELS MUST BE CLOSED
OVER PEGS BEFORE TIGHTENING

1. TIGHTEN FOUR BOLTS ON HORIZONTAL SIDEWALL SEAMS.
2. TIGHTEN BOLTS WHERE TOP TWO DOOR PANELS MEET.
3. TIGHTEN REMAINING BOLTS UNIFORMLY AROUND DOOR.



SWB0056
 12/05/2019 CLW







Fig. 2

Loosely bolt hinge support pieces (B53421) to bin wall and door frame as shown in Fig. 3. Hinge support pieces are shown in relation to door pegs.



Slide hinge supports up until they touch hinge braces (B53341). Fig. 4 shows that all hinge braces are above hinge supports.



HINGE BRACE WILL BE ADJUSTED FROM SIDE TO SIDE AS NEEDED BASED ON BIN DIAMETER.

Loosen 3/8" bolts and slide hinge braces over until hinge holes line up with holes in hinge supports. See Fig. 5. Insert a 3/8" bolt through each hole and turn nut on loosely.


Tighten nuts connecting hinge braces to door and hinge supports to door frame.

Use 3/8 x 1" hex-head bolts, flat washers, and lock nuts to attach hinge braces to hinge supports. Turn lock nuts all the way onto hinge bolts, then back them off until door panels swing freely. Ensure door panels close securely over pegs.

Install outer door with hinges in desired direction. Adjust hinges as needed.

Install door catch. See Fig. 6. Remove and use existing bolt for mounting catch, or field-drill hole into bin sidewall if an existing bolt is not in correct spot.

Attach doorstep below door. It may be possible to align some bolt holes with those in bin sidewall. If not, field-drill four (4) mounting holes. Use 3/8" hardware to attach doorstep to bin.



NOTE: Bolt splice bracket B5461 to corners of 44" doors on 36' diameter and larger bins to help strengthen door corners. Attach as shown in Fig. 7 using 3/8 x 1" bolts that are used for connecting sidewall sheets to frame. Make sure bracket attaches to two holes of each sidewall sheet.





Fig. 7

Safety Catch prevents latching of outer door unless inner panels are securely closed. After installation of door as shown on previous pages, final adjustment is required to ensure latches on outer door skin fit securely in catches on hammer-head latches of inner door panels.

Fig. 8 provides overview (66" door is shown; 44" installs similarly).



Ensure catch (B5494) that was factory-attached to hammer-head latch will protrude through factory-cut rectangular hole in door skin when inner door panels are closed. Image 1 shows catch.

Attach foam (K6843) to inside of door around slot as shown in Image 2 to provide watertight seal.

Close outer door (skin) and pull down its handle so that latch fits securely into catch as shown in Fig. 8.

If need be, loosen bolts attaching catch to hammer-head latch. See Image 1. Slots in catch and hammer-head latch allow for adjustment. Position catch for proper fit and retighten hardware.

Double-check fit by opening outer and inner doors and then closing inner panels and outer door.

Adjust again as needed.

Repeat process above for lower catch.

NOTE: If door will be installed to open from left to right, attach B5494 catches to hammer-head latches (B5319) on left side of inner door panels and follow steps above to ensure fit.




Image 1 – Catch bolted to hammer-head latch





Image 2 – Foam sealant (K6843) on inside of door

Components of 66" Door

Fig.9 and Table 1 show components of 66" door. Components of 44" door are similar, with only two inner door panels.



SWB0345
07/21/2023 JLT

Fig. 9 & Table 1

ITEM #	DESCRIPTION	PART #	QTY.
1	Door assy., 66", 36-48' dia. bin	B5323	1
2	Top inner door	B53321	1
3	Middle inner door	B5332	1
4	Bottom inner door	B5333	1
5	Inner door latch bracket	B5314	6
6	Outer door hinge	J2274	2
7	Inner door latch, left	B5318	3
8	Inner door latch, right	B5319	3
9	Inner door latch arm	B5091	3
10	Inner door hinge brace	B53341	6
11	Inner door hinge support	B53421	6
12	Bin door peg, HD	B53432	36
13	Jam nut, 5/8" – 11	J1048	36
14	Catch	B5494	2
15	Outer door, 66"	B5331	1
16	Outer door cross bar	B5328	2
17	Outer door handle bracket	B5356-01	2
18	Outer door handle	B5356-02	1

Ladders, Safety Cages & Platforms

Locations of roof stairs, sidewall ladder and platforms are critical factors in constructing a grain bin. Consider positions in relation to overall layout of site and auxiliary equipment. Location of manhole and roof stairs will establish locations of sidewall ladder, manhole platform and roof stairs platform.

Instructions in this section are for standard (S-Option) ladders package. Maximum distance between platforms is 30'. If B-Option package (22' max distance between platforms) was ordered, see instructions in L13916. See L13915 if fall-arrest cable system was ordered for bin.

DISCLAIMER: It shall be the sole responsibility of the customer to determine applicability of federal Occupational Safety and Health Administration (OSHA) fall protection rules at bin site. Sukup Manufacturing Co. will not be responsible for any personal injury or loss resulting from failure to comply or from incorrect installation or use of fall protection equipment.



WARNING: When installing ladder sections, rung treads must face upward. Failure to heed this warning may cause death or serious injury.

Inside Ladder & Angled Standoff Brackets (Sukup Farm-Duty Bins)

Ladder should be centered under manhole. Attach to sidewall with angled inside ladder splice brackets (B50791) at every horizontal seam. The only exception will be at top of each ladder, where brackets must be moved down 4" to avoid interference with roof sheet and ladder caps. Bins with stirring machine will be shipped with a 33" ladder that attaches below stirring machine track. See Fig. 1. Every sidewall ring except bottom one will have ladder attached to it.




Fig. 1

Use 3/8" hardware to attach inside ladder. Insert bolts from outside of bin to create a watertight seal. If outside ladder brackets will be used at exact same location, remove washer and place between outside bracket and sidewall.

Inside Ladder & 90° Standoff Brackets (Sukup Commercial Bins)

Ladder should be centered under manhole. Attach to sidewall with 90° inside ladder splice brackets (B5079) at every horizontal seam. See Fig. 2. The only exception will be at top of each ladder, where brackets must be moved down 4" to avoid interference with roof sheet and ladder caps. Every sidewall ring except bottom one will have ladder attached to it.




Fig. 2


Use 3/8" hardware to attach inside ladder. Insert bolts from outside of bin to create a watertight seal. If outside ladder brackets will be used at exact same location, remove washer and place between outside bracket and sidewall.

Additional Inside Ladder Support Brackets

Bin Height	Set(s) of Support Brackets	Horizontal Seam Used for Bracket Attachment*
6-12	1	2nd
13-18	2	2nd, 6th
19-24	3	2nd, 6th, 10th
25-29	4	2nd, 6th, 10th, 14th
30	5	2nd, 6th, 10th, 14 th , 18th

*Location determined by counting seams from bottom as shown in Fig. 3. Do not count base angle seam.

Fig. 3





To provide added stability to inside bin ladders, one to five pairs of support brackets (B5110) are provided, depending on height of bin. One pair should be installed in bins with 6 to 12 rings; two pairs in bins with 13 to 18 rings; three pairs in bins with 19 to 24 rings; four pairs in bins with 25 to 29 rings, and five pairs in bins with 30 rings. See guidelines above for attaching locations. Some examples: A 10-ring bin requires one (1) set of ladder support brackets attached at 2nd horizontal seam; a 14-ring bin requires two (2) sets of ladder support brackets, attached at 2nd and 6th horizontal seams; a 22-ring bin requires three (3) sets of ladder support brackets, attached at 2nd, 6th, & 10th horizontal seams.

Install brackets at ladder splice, using existing horizontal seam bolt in middle hole of support bracket. Field-drill one hole above and one hole below horizontal seam as shown in Fig. 3 and secure with 3/8" hardware. Bolts should be inserted from outside of bin. Attach brackets to inside of ladder rails as shown, using holes provided and 3/8" hardware. **TIP:** It may help to mark on supplied color chart the locations of these additional ladder support brackets.

NOTE: Horizontal seams are at top of specified ring. Do NOT count base angle seam.

Outside 44" Ladders

44" ladder sections attach at each sidewall ring. Attach ladders to sidewall with outside ladder splice brackets (B5078) at every horizontal seam. The only exception will be at top and bottom of each ladder assembly. Splice brackets must be moved up or down 4" to avoid interference with roof sheets, platform brackets, concrete and ladder caps. See Fig. 4.



NOTE: 3/8" hardware is used to assemble all ladders, platforms and cages.

Insert splice bracket bolts from inside of bin to create a watertight seal. If inside ladder brackets are used at exact same location, remove washer and place between outside bracket and sidewall. See Fig. 5.

Ladder Extension (B5020)

Ladder extensions (B5080) are provided with cage and platform packages. Extensions are an option for 3-5 ring ladder packages.





Fig. 6

Ladder extensions (B5080) are provided as a means to walk “through” ladder onto roof steps. Extensions are connected to ladder rails using offset extension brackets (B5081). When attaching extension bracket to ladder, hardware will be inserted through three (3) pieces (extension bracket, ladder siderail and ladder bracket). Align extension bracket with top holes on ladder siderail as shown in Fig. 6, then attach ladder bracket to siderail and extension bracket. Attach other end of ladder bracket to sidewall. Attach ladder extensions to extension brackets and stabilize to roof ribs using extension braces. See Fig. 6. Attach with 3/8” hardware. Slide plastic ladder caps over tops of extensions. **NOTE:** Field drilling may be required when attaching extension braces. Extension braces (B5082) may need to be attached by a different means to avoid interference with manhole.


Extension and Standard D-ring

Fig. 7 shows differences between an extension D-ring (B5089) and a standard D-ring (B5085). Extension D-rings are used only with ladder extensions. Standard D-rings are used only on ladders. Both D-rings have same outside dimensions. Differences are at connection points. See Details A & B of Fig. 7.

EXTENSION D-RING



STANDARD D-RING



SWBL0018
2/27/2007BAP

Fig. 7

Ladder Cage/No Platform




Fig. 8

Some ladder and cage assemblies do not require use of platforms. For these, an extension package is available as an option to access roof steps. If safety cage is used on these ladders, extension D-rings (B5089) are required. They attach to ladder extensions as shown in Fig. 8. Connect platform uprights (B5092) to D-rings with 3/8" hardware and tighten. See Fig. 8. Attach extension braces (B5082) as shown to avoid interference with manhole. If no manhole is present, both braces can be attached at same height on roof ladder.

44" Cages with 22" Flared Bottoms




Fig. 9

As bin is built, continue to add appropriate ladder and cage sections. Refer to following pages for specific ladder and cage layouts. Cage sections consist of standard D-rings (B5085) and seven (7) 44" uprights (B5090). Standard D-rings attach to inside of ladder siderails. A flared D-ring is always used at bottom of each cage assembly. Top D-ring must be connected to center of top ladder. This allows bottom flared D-ring to be at proper height above the next surface (concrete or platform). Attach standard D-rings and uprights to ladder sections with 3/8" hardware. See Fig. 9.

36" Platform Locations

Fig. 10 shows the four (4) positions where platform can be located. **NOTE:** Each location is at same level as a ladder rung in first ring. For 1st & 2nd positions, 44" sidewall bracket mounts to sidewall at horizontal seams and in middle of sidewall sheet. For 3rd & 4th positions, middle hole of 44" sidewall bracket mounts at horizontal seam and top and bottom of bracket are attached in middle of sidewall sheets. Field drilling is required.




Fig.10

36" Platform Starting Location

Location of ladder is a critical factor in constructing a grain bin. Careful thought must be given to position of sidewall and roof ladders in relationship to overall layout of site and auxiliary equipment. Location of roof ladder and manhole during bin construction will establish location of sidewall ladder. Sidewall ladder and eave platform must be in line with roof ladder and manhole. Fig. 11 shows eave platform starting location on a sidewall sheet with 9-3/8" bolt hole spacing. Lower drawing shows ladder centered between stiffeners.

IMPORTANT: When attaching ladder and safety cages to a stiffened bin, locate ladder between two (2) stiffeners. When constructing bin with raftered substructure, be certain manhole is not aligned over a rafter. Suggestion: Locate roof ladder on roof sheet to right of primary rafter. Manhole can then be placed on sheet to right of roof ladder. This ensures that eave platform will be centered over a stiffener. Platforms are designed to ensure that when additional ladder columns are offset, they are not centered over a stiffener.





Fig. 11



SWBL0001
06/02/2014 JLT

36" Platform Assembly




Fig. 12

Entire platform assembly is constructed with 3/8" hardware. Begin by attaching sidewall brackets (B5096) to sidewall. Some holes may need to be field-drilled in sidewall depending on which position was chosen for platform. Attach platform supports (B5097) and sidewall braces (B5098) to sidewall brackets as shown in Fig. 12. **NOTE:** Leave all bolts loose until assembly is complete.

Attach platform (B5095) to platform supports and fasten corner posts (B5112) to 4" toeboard. Fasten long and short platform handrails to corner posts. See Fig. 12. Tighten platform assembly. **HINT:** If assembling platform with safety cages, corner post brace (B5109) and post that it braces can be left off of platform assembly at this time.

Top & Bottom Corner Posts, 36" Platform

Fig. 13 shows the four locations platform can be positioned. Top and bottom corner posts will not be moved vertically. Only the platform assembly itself will be able to move up or down on corner posts. **NOTE:** Top half D-ring fastens to top hole in top corner post and bottom half D-ring fastens to bottom hole of bottom corner post.




Fig. 13

Eave Platform Cage, 36" Platform




Fig. 14

When attaching cage to platform, half D-rings (B5087 & B5088) must attach to corner posts (B5105 & B5106) as shown in Fig. 14. **NOTE:** If platform is mounted in 1st or 2nd position, attach cage extension as shown in Detail A. If platform is mounted in 3rd or 4th position, top half D-ring adapter (B5107) and three uprights are not used. See Detail A-1. Attach remaining upright to half D-ring B5087.

Eave Platform Cage Assembly, 36" Platform




Fig. 15

Final attachment of cage to extensions and platform is shown in Fig. 15. Platform is shown in 2nd position. All cage and platform assemblies are connected with 3/8" hardware. Remove D-ring overlaps as shown in Detail A to ensure smooth, snag-free edges.

NOTE: Six (6) platform uprights and five (5) 44" uprights are sent with this assembly. Depending on diameter of bin, one upright may be discarded at each location where half D-rings connect to corner post. Be certain that gap is no more than 9".

See Fig. 9 and related instructions for adding ladder and cage sections.

54" Landing Platform Layout for Non-Stiffened Bin




Fig. 16

Fig. 16 shows where flared D-ring should be attached in relation to 54" landing platform on a non-stiffened bin. Flared D-ring should be two (2) sidewall rings above platform. **Platform must be attached to sidewall in 1st position.** This will ensure that federal Occupational Safety and Health Administration (OSHA) standards are met, as well as ease erection of ladder and cages. Two ladders attach to sidewall on same ring at platform location. At top and bottom of each ladder assembly, sidewall brackets need to be moved either up or down 4" to avoid interference with roof sheets, platform brackets, concrete and ladder caps.

54" Landing Platform with Caged Ladder




Fig. 17

Attach 54" landing platform to sidewall under upper ladder as shown in Fig. 16. Attach 44" ladder section to sidewall ring above platform. Fasten corner post extension, B5093, to bottom of open-faced corner post B5111 as shown in Fig. 17. Note that corner post B5111 is slightly longer than B5112 posts. Placement is critical.

Attach half D-rings to inside of ladder siderail and fasten them to corner post B5111 and corner post extension, B5093. Connect safety cage uprights to half D-rings with 3/8" hardware and tighten. Slide ladder caps over siderails of top ladder section. See Fig. 17. Also, remove half D-ring overlaps as shown in Detail A to ensure smooth, snag-free edges.

Manhole & Roof Platform Locations

Deck of manhole platform should be even with second ladder rung below eave. Deck of roof stairs platform should be even with first ladder rung above eave. See Fig. 18. Sidewall brackets for both platforms mount at horizontal seams and at middle of sidewall sheet. Field-drilling is required. Detailed assembly instructions for platforms can be found elsewhere in this section.




Fig. 18 – Manhole platform & roof stairs platform positions

NOTE: Roof stairs platform is also known as a lifted platform. It sits on a riser.

Positioning Ladder & Platforms on Bin with 2 Stiffeners per Sidewall Sheet

See Figs. 19 and 20 for positioning of ladder and platforms on bin with two stiffeners per sidewall sheet. Fig. 19 shows positioning when three roof sheets attach per sidewall sheet. Fig. 20 shows positioning when four roof sheets attach per sidewall sheet. In both cases, ladder must be centered between stiffeners.

IMPORTANT: If bin has raftered substructure, ensure manhole is not positioned over a rafter. An intermediate rafter under a manhole can be removed.




Fig. 19 – Ladder & platform locations with 2 stiffeners & 3 roof sheets per sidewall sheet




Fig. 20 – Ladder & platform locations with 2 stiffeners & 4 roof sheets per sidewall sheet

Positioning Ladder & Platforms on Bin with 3 Stiffeners per Sidewall Sheet

See Figs. 21 and 22 for positioning of ladder and platforms on bin with three stiffeners per sidewall sheet. Fig. 22 shows positioning when three roof sheets attach per sidewall sheet. Fig. 23 shows positioning when four roof sheets attach per sidewall sheet. In both cases, ladder must be centered between stiffeners.

IMPORTANT: If bin has raftered substructure, ensure manhole is not positioned over a rafter. An intermediate rafter under a manhole can be removed.




Fig. 22 – Ladder & platform locations with 3 stiffeners & 3 roof sheets per sidewall sheet




Fig. 23 – Ladder & platform locations with 3 stiffeners & 4 roof sheets per sidewall sheet

Roof Stairs (Lifted) 54" Platform




Fig. 25

Assemble roof stairs (lifted) 54" platform as shown in Fig. 25 using 3/8" hardware. Begin by attaching sidewall brackets (B5096) to sidewall. Some holes may need to be field-drilled in sidewall. Attach platform supports (B5097) and brace angles (B5098) to sidewall brackets as shown. **NOTE:** Leave all bolts loose until assembly is complete.

Assemble platform riser and step as shown in Fig. 25. Attach to platform supports as shown.

Attach platform (B5103) to platform riser and fasten corner posts (B5112) to 4" toeboard. Fasten platform handrails to corner posts as shown. Also attach corner post brace (B5109) as shown.

Eave Platform Cage, 54" Platform




Fig. 26

When attaching cage to platform, half D-rings (B5087) must attach to top and bottom corner posts (B5105 & B5106) as shown in Fig. 26. Attach half D-ring adaptors (B5107) to ladder as shown.

Connection of 54" Manhole & Roof Stairs Platforms

Connection of platforms is shown in Fig 27. Manhole platform (lower) is shown in 2nd position. Roof stairs (lifted) platform is shown in 1st position. Platforms are connected with 3/8" hardware.




Fig. 27

Use step handrail post (B5206) and short handrails (B5101) to close gap between platforms. See Fig. 28. **NOTE:** Gap will depend on radius of bin.




Fig. 28

See Fig. 9 and related instructions for adding ladder and cage sections.

54" Landing Platform Layout for Stiffened Bin




Fig. 29

Fig. 29 shows where flared D-ring should be attached in relation to 54" landing platform on a stiffened bin. Flared D-ring should be two (2) sidewall rings above platform. **Platform must be attached to sidewall in 1st position.** This will ensure that OSHA standards are met, as well as ease erection of ladder and cages. Two ladders attach to sidewall on same ring at platform location. At top and bottom of each ladder assembly, sidewall brackets need to be moved either up or down 4" to avoid interference with roof sheets, platform brackets, concrete and ladder caps.

To ensure that additional ladder columns will be centered between two stiffeners, attach platform to sidewall as shown in Fig. 29. Top ladder column should have already been centered between two stiffeners.

54" Landing Platform with Cage





Fig. 30

Attach 54" landing platform to sidewall under upper ladder as shown in Fig. 29. Attach 44" ladder section to sidewall ring above platform, centered between two stiffeners. Fasten corner post extension, B5093, to bottom of open-faced corner post B5111 as shown in Fig. 30. Note that corner post B5111 is slightly longer than B5112 posts. Placement is critical.

Attach half D-rings to inside of ladder siderail and fasten them to corner post B5111 and corner post extension, B5093. Connect safety cage uprights to half D-rings with 3/8" hardware and tighten. Slide ladder caps over siderails of top ladder section. See Fig. 30. Also, remove half D-ring overlaps as shown in Detail A to ensure smooth, snag-free edges.

Ladder Layout, 3-Ring to 5-Ring Bin



SWBL0037
7/11/2007KJZ

Fig. 31

Ladder & Cage Layout, 6-Ring to 8-Ring Bin





Fig. 32

Ladder & Cage Layout, 9-Ring to 12-Ring Bin



SWBL0083
1/3/19 AJS

Fig. 33

Ladder & Cage Layout, 9-Ring to 16-Ring Bin




Fig. 34

Ladder & Cage Layout, 17-Ring to 24-Ring Bin




Fig. 35

Ladder & Cage Layout, 25-Ring to 30-Ring Bin





Fig. 36

Ladder Platform Swing Gate

Use drawings and parts list below to assemble ladder platform swing gate.



ITEM #	DESCRIPTION	QTY.	PART #
1	Hinge plate	1	BSG0003
2	Rail tubing	2	BSG0001
3	Hinge bracket	2	BSG0004
4	Torsion spring	2	J23832
5	Screw, 5/16 – 18 x 4"	2	J0598
6	Flange nut, 5/16"	16	B5922
7	U-bolt, 5/16 – 18 x 2", 1-1/4" ID	4	J0556
8	Screw, 5/16 – 18 x 3/4"	4	J0522
9	Screw, 5/16 – 18 x 2"	2	J0584
10	Rail splice	1	BSR1015

Fig. 37

Assemble swing gate and attach to hinge plate using U-bolts (J0556) and 5/16" flange nuts (B5922).

Field-drill holes in upright for attachment of hinge brackets (BSG0004). Top of upper bracket should be 4-1/2" from top of handrail as shown in Fig. 38.

Fasten hinge brackets to upright with 5/16 – 18 x 3/4" screws (J0522) and 5/16" flange nuts (B5922).




Fig. 38



Note: Assembly Instructions for Greene Sidewall Stairs are located in one of the platform bundles sent with the sidewall stair packages, see below

Easy Step


Assembly Instruction Location **(B)ES3544** PLATFORM,STAIR&TOP SECT,44"RG

C-Farm Series

Assembly Instruction Location **(B)CF3544L** PLATFORM,STAIR,LONG,CF-SERIES

C-Commercial Series

Assembly Instruction Location **(B)CC3544L** PLATFORM,STAIR,LONG,CC-SERIES



L13921